Virtual Regular Meeting of the Mayor and Council of the Borough of Bogota, to be held at the Bogota Council Chambers, 375 Larch Avenue, Bogota, NJ, on Thursday, August 19, 2021 at 7:30pm.

Join Zoom Meetinhttps://us02web.zoom.us/j/82450037385
Meeting ID: 824 5003 7385
Passcode: 780798
One tap mobile
+13017158592,,82450037385#,,,,*780798# US (Washington DC)
Dial by your location
+1 929 205 6099 US (New York)
Meeting ID: 824 5003 7385
Passcode: 780798
Find your local number: https://us02web.zoom.us/u/kcXgOwlLyh

Salute to the Flag

The notice requirements of the Open Public Meetings Law have been satisfied as notice was sent to two newspapers and posted on the Borough Hall bulletin board on July 7, 2021.

Roll Call: Mayor Kelemen, Councilmembers Carpenter, Connors, Fede, Granquist, Murphy, and Robbins, and Borough Attorney, Borough Administrator

Citizen Remarks: One Five (5) minute time limit per person

Presentation: Tax Assessor Patrick Wilkins will explain the tax map situation and revaluation of the Borough.

Discussion: -Safety Plan regarding Railroads with input from Police, OEM, and Fire Prevention

Consent Agenda
21-134 Amend Interlocal Agreement for SLEOIIIs for 2021-2022
21-135 Supporting Drive Sober or Get Pulled Over 2021 Statewide Labor Day Crackdown

Resolutions to be voted on Separately:
PC21-13 Payment of Claims

At the July 15, 2021 meeting, the following Motion was made by Councilwoman Murphy, seconded by Councilwoman Carpenter, and then tabled for Discussion at the 8/19/2021:
Motion to Move Forward and Accept Bid for New Recycling Center and Take Necessary Next Step

Introduction of Ordinance:
#1566 An Ordinance Amending Chapter 7A of the Bogota Code Entitled "Traffic Schedule"

Public Hearing of Ordinance:

#1565 An Ordinance Amending Chapter 21b of the Code Of the Borough Of Bogota, Entitled "Stormwater Control"

Approvals - Cindy Cross is requesting a Block Party for August 21, 2021 at 232 Beechwood Avenue from Queen Anne Road to Dunn Avenue from 2PM to 5PM.

- Roselyn Holland is requesting a Block Party for August 21, 2021 on James Street between East Fort Lee Road and Central Avenue from 3PM to 9PM.
- St. Joseph Church is requesting approval for a bingo license for September 19, 2021, a raffle license for a prize wheel for September 18 and 19, and a raffle license for tear off 50/50s for September 18 and 19 for a Church Festival with Borough fees waved.
- Minutes 7/15/2021, Closed Session Minutes 7/15/21

Citizen Remarks: One Five (5) minute time limit per person

Reports: Mayor, Council Committees, Borough Administrator, Borough Attorney, Borough Clerk

Closed Session – Redevelopment
-- Litigation

Adjournment

RESOLUTION # 21-134 DATE: 8/19/2021

COUNCIL	YES	NO	ABSENT	ABSTAIN	MOTION	SECOND
C. Carpenter						
M. Connors						
D. Fede						
J.E. Granquist						
M.E. Murphy						
R. Robbins						

Amending Interlocal Agreement for SLEOIIIs for 2021-2022

WHEREAS, the Borough of Bogota (hereinafter the "Borough") and the Bogota Board of Education (hereinafter the "Board") had entered into an Interlocal Service Agreement (the "Agreement") for the Borough to provide Class Three Special Law Enforcement Officers to the Board's schools for the 2019-2021 school years, in accordance with the provisions of N.J.S.A. 40A:14-146.10-11, the Uniform Shared Services and Consolidation Act and other applicable laws; and,

WHEREAS, pursuant to Article V(A)(b) of the Agreement, the parties have agreed to extend the term of the Agreement for an additional three year period, to expire on June 30, 2024 (hereinafter the "extended term"); and,

WHEREAS, a document entitled "Addendum to the Interlocal Services Agreement between the Bogota Board of Education and the Borough of Bogota" (hereinafter the "Addendum") was prepared to memorialize the term extension, and to make other agreed upon amendments to the Agreement that will take effect during the extended term; and,

WHEREAS, a copy of the Addendum is attached herein as an Exhibit; and,

WHEREAS, unless expressly modified by the Addendum, the terms contained in the Agreement shall remain in full force and effect between the Borough and the Board during the extended term; and,

WHEREAS, the Mayor and Council desire to execute the Addendum upon the terms set forth herein.

NOW, THEREFORE, BE IT RESOLVED by the Mayor and Council of the Borough of Bogota, that the document entitled "Addendum to the Interlocal Services Agreement between the Bogota Board of Education and the Borough of Bogota" is hereby approved; and,

BE IT FURTHER RESOLVED, that the Mayor, Borough Clerk, Borough Administrator and/or any other necessary Borough officials are hereby authorized to execute the aforementioned Addendum, and to carry out the terms set forth therein; and,

BE IT FURTHER RESOLVED, that a copy of the fully executed Addendum shall be forwarded to all parties, and to the Division of Local Government Services of the Department of Community Affairs for filing.

21-134

ADDENDUM TO THE INTERLOCAL SERVICES AGREEMENT BETWEEN THE BOGOTA BOARD OF EDUCATION AND THE BOROUGH OF BOGOTA

WHEREAS, the **BOGOTA BOARD OF EDUCATION** (hereinafter, the "Board") and **BOROUGH OF BOGOTA** (hereinafter, the "Borough") are parties to an Interlocal Services Agreement for Class Three Special Law Enforcement Officers ("SLEOIIIs or SLEOIII" as the case may require) originally entered from June 27, 2019 through June 30, 2021 (hereinafter referred to as the "Agreement") under which the Borough would provide three (3) SLEOIII officers to the Board to serve at Steen School, Bixby School, and Bogota High School; and

WHEREAS, the parties seek to continue and extend the Agreement for a three (3) year term, under Article V(A)(b) of the Agreement, through June 30, 2024; and

WHEREAS, the parties also seek to amend the Agreement to permit the assignment of an additional SLEOIII to be assigned to Bogota Middle School;

NOW THEREFORE, based on the premises and mutual promises and covenants contained herein and in the Agreement, and for good and valuable consideration, the receipt of which is hereby acknowledged, the parties amend the Agreement as follows:

1. **Article I. <u>Obligations of the Borough</u>**, subsection A shall be amended to read as follows:

   "The Borough agrees to provide SLEOIIIs to render services to the District for no less than 182 days per school year (September to June) and during the Summer months, as needed and upon prior notice by the Board to the Borough

21-134

July 1, 2021 through June 30, 2024" (hereinafter referred to as "Term" or "School Year Term").

4. This Addendum is to be incorporated into and made a part of the Agreement. The Agreement is hereby modified as set forth herein.
5. Except as expressly modified herein, the Agreement shall remain unchanged and in full force and effect.

IN WITNESS WHEREOF, the parties hereunto caused these presents to be signed by their proper corporate officers and caused their proper corporate seals to be hereunto affixed, the day and year first above written.

ATTEST:

BOGOTA PUBLIC SCHOOLS DISTRICT BOARD OF EDUCATION

By:_____
Irfan Evcil
Business Administrator/
Board Secretary

By:_____
KATHY VAN BUREN
Board President

ATTEST:

BOROUGH OF BOGOTA

By:_____
Jeanne M. Cook
Clerk

By:_____
CHRISTOPHER M. KELEMEN
Mayor

21-134

EXTRACT FROM THE MINUTES OF A MEETING OF THE BOGOTA BOARD OF EDUCATION OF THE BOROUGH OF BOGOTA BERGEN COUNTY, NEW JERSEY AS RECORDED IN THE OFFICIAL MINUTES BOOK

The Board of Education of the Borough of Bogota, in the County of Bergen, New Jersey, convened in a Virtual Public Meeting on June 30, 2021.

The following members of the Board of Education were present: Mrs. Kohles, Mr. Miranda, Ms. Montgomery, Mr. Chavez and Mrs. VanBuren.

Absent: Mrs. Alvarez, Mrs. Lewis, Mr. Ortega and Ms. Ruckett.

Motion by: Mr. Miranda **Seconded by: Mrs. Kohles**

Approval of Addendum for Interlocal Service Agreement

6-30-21-06 **BE IT RESOLVED,** that, upon the recommendation of the Superintendent of Schools, the Board approves the Addendum for Interlocal Service Agreement between the Borough of Bogota and the Bogota Board of Education for class three special law enforcement officers to continue and extend agreement for a (3) year term through June 30, 2024, as per the attached.

AYES: Mrs. Kohles, Mr. Miranda, Ms. Montgomery, Mr. Chavez and Mrs. VanBuren.

NAYES: None.

State of New Jersey, County of Bergen

I, Irfan Evcil, Board Secretary of the Bogota Board of Education, of the Borough of Bogota, in the County of Bergen, State of New Jersey, hereby certify that the foregoing extract from the minutes of the Meeting of the Board of Education of said District, duly called and held on June 30th, 2021, has been compared by me with the original minutes as officially recorded in my office of said Board of Education as a true, complete copy thereof and of the whole of said original minutes, so far as they relate to the subject matter referred to in said extract, in witness I have hereunto set my hand and affixed the Corporate Seal of said Board of Education on this 1st day of July 2021.

Irfan Evcil
Business Administrator/Board Secretary

RESOLUTION # 21-135 DATE: 8/19/2021

COUNCIL	YES	NO	ABSENT	ABSTAIN	MOTION	SECOND
C. Carpenter						
M. Connors						
D. Fede						
J.E. Granquist						
M.E. Murphy						
R. Robbins						

Supporting the *Drive Sober or Get Pulled Over 2021 Statewide Labor Day Crackdown*

Whereas, approximately one-third of all fatal traffic crashes in the United States involve impaired drivers; and

Whereas, impaired driving crashes killed 10,142 people in the United States in 2019; and

Whereas, impaired driving crashes cost the United States almost $44 Billion a year; and

Whereas, during the past five years New Jersey's roadways experienced 35,307 crashes and 618 fatalities involving impaired drivers; and

Whereas, an enforcement crackdown is planned to combat impaired driving; and

Whereas, the end of summer/Labor Day period is traditionally a time for social gatherings which include alcohol; and

Whereas, the State of New Jersey, Division of Highway Traffic Safety, has asked law enforcement agencies throughout the state to participate in the *Drive Sober or Get Pulled Over 2021 Statewide Labor Day Crackdown*; and

Whereas, the project will involve increased impaired driving enforcement from August 20, 2021 through September 6, 2021; and

Whereas, an increase in impaired driving enforcement and a reduction in impaired driving will save lives on our roadways;

Therefore, be is resolved that the Borough of Bogota Mayor and Council declares it's support for the *Drive Sober or Get Pulled Over 2021 Statewide Labor Day Crackdown* from August 20, 2021 through September 6, 2021 and pledges to increase awareness of the danger of driving while impaired by alcohol or drugs.

RESOLUTION # PC21-13 DATE: 8-19-21

COUNCIL	YES	NO	ABSENT	ABSTAIN	MOTION	SECOND
C. Carpenter						
M. Connors						
D. Fede						
J.E. Granquist						
M.E. Murphy						
R. Robbins						

WHEREAS, as required by NJSA 40A:4-57 and any other applicable requirements, the Chief Financial Officer of the Borough of Bogota has certified there are sufficient funds available in the appropriations of the municipal budget line items to make payment too claimants per the payment of claims;

BE IT RESOLVED that the Mayor and Council of the Borough of Bogota authorizes payment in the aggregate amounts of:

Fund	Amount
Total fund 01 CURRENT FUND	2,590,055.48
Total fund 04 General Capital Fund	34,854.00
Total fund 14 Trust Fund	34,830.00
Total fund 17 PAYROLL	1,069.95
GRAND TOTAL:	2,660,809.43

Bills List

BOROUGH OF BOGOTA

08/17/21 04:28:19 PM

PO Number	Po Date	Vendor	Description		Amount	Paid Date
01-2010-20-1001-000 Appropriation Control General Administration - S&W Salary &						
210728	07/14/21	BOROUGH OF BOGOTA	2021-07-15 PR		5,980.95	07/14/21
210740	07/27/21	BOROUGH OF BOGOTA	2021-07-30 PR		5,980.95	07/27/21
210821	08/11/21	BOROUGH OF BOGOTA	2021-08-13 PR		5,980.95	08/11/21
Total for	Appropriation Control General Administration -			17,942.85		
Department Total: Appropriation Control General Administration -				17,942.85		
01-2010-20-1002-001 Appropriation Control General Administration - O/E Water Cooler						
210101	02/03/21	AQUA CHILL PARSIPPANY	76167, JUNE 2021 WATER COOLER		142.00	08/17/21
Total for	Appropriation Control General Administration -			142.00		
01-2010-20-1002-002 Appropriation Control General Administration - O/E Miscellaneous						
210743	07/29/21	PHOENIX ADVISORS, LLC	REDEVELOPMENT PROJECT QTR ENDING		612.50	08/17/21
Total for	Appropriation Control General Administration -			612.50		
Department Total: Appropriation Control General Administration -				754.50		
01-2010-20-1101-000 Appropriation Control Mayor & Council - S&W Salary & Wages						
210728	07/14/21	BOROUGH OF BOGOTA	2021-07-15 PR		919.06	07/14/21
210740	07/27/21	BOROUGH OF BOGOTA	2021-07-30 PR		744.18	07/27/21
210821	08/11/21	BOROUGH OF BOGOTA	2021-08-13 PR		744.18	08/11/21
Total for	Appropriation Control Mayor & Council - S&W			2,407.42		
Department Total: Appropriation Control Mayor & Council - S&W				2,407.42		
01-2010-20-1201-000 Appropriation Control Municipal Clerk - S&W Salary & Wages						
210728	07/14/21	BOROUGH OF BOGOTA	2021-07-15 PR		7,146.90	07/14/21
210740	07/27/21	BOROUGH OF BOGOTA	2021-07-30 PR		5,735.31	07/27/21
210821	08/11/21	BOROUGH OF BOGOTA	2021-08-13 PR		5,702.83	08/11/21
Total for	Appropriation Control Municipal Clerk - S&W			18,585.04		
Department Total: Appropriation Control Municipal Clerk - S&W				18,585.04		
01-2010-20-1202-000 Appropriation Control Municipal Clerk - O/E Other Expenses						
210833	08/17/21	NORTH JERSEY MEDIA GROUP	VARIOUS PUB NOTICEMAY 2021 - SEE		870.80	08/17/21
Total for	Appropriation Control Municipal Clerk - O/E			870.80		
Department Total: Appropriation Control Municipal Clerk - O/E				870.80		
01-2010-20-1301-000 Appropriation Control Financial Administration - S&W Salary &						

Bills List

BOROUGH OF BOGOTA

08/17/21 04:28:19 PM

PO Number	Po Date	Vendor	Description		Amount	Paid Date
210728	07/14/21	BOROUGH OF BOGOTA	2021-07-15 PR		3,056.76	07/14/21
210740	07/27/21	BOROUGH OF BOGOTA	2021-07-30 PR		733.24	07/27/21
210821	08/11/21	BOROUGH OF BOGOTA	2021-08-13 PR		733.24	08/11/21
Total for	Appropriation Control Financial Administration			4,523.24		
Department Total: Appropriation Control Financial Administration				4,523.24		
01-2010-20-1302-000 Appropriation Control Financial Administration - O/E Other						
210099	02/03/21	BATTAGLIA ASSOCIATES, LLC.	BO-2021-07 JUL FINANCIAL & TAX		9,180.00	08/17/21
210809	08/10/21	CMRS-FP	POSTAGE		2,000.00	08/10/21
Total for	Appropriation Control Financial Administration			11,180.00		
01-2010-20-1302-002 Appropriation Control Financial Administration - O/E Payroll						
210765	08/02/21	ACTION DATA SERVICES	DEMAND DEBIT - 08/02/2021		414.19	08/02/21
210815	08/05/21	ACTION DATA SERVICES	DEMAND DEBIT - 08/05/2021		919.40	08/05/21
210830	08/13/21	ACTION DATA SERVICES	DEMAND DEBIT - 08/13/2021		516.07	08/13/21
Total for	Appropriation Control Financial Administration			1,849.66		
Department Total: Appropriation Control Financial Administration				13,029.66		
01-2010-20-1352-000 Appropriation Control Audit Services - O/E Other Expenses						
210696	07/13/21	WIELKOTZ & COMPANY, LLC	21-18-01510; PROGESS BILLING #2;		15,000.00	08/17/21
Total for	Appropriation Control Audit Services - O/E			15,000.00		
Department Total: Appropriation Control Audit Services - O/E				15,000.00		
01-2010-20-1402-001 Appropriation Control Data Processing - O/E Miscellaneous						
210727	07/13/21	DELL MARKETING L.P.	10508199212, REPLACEMENT MODEM		1,681.87	08/17/21
210746	07/29/21	PITNEY BOWES	8000-9000-0132-8594, POSTAGE		1,096.09	08/17/21
210742	07/29/21	TRI-STATE TECHNICAL	31289, AUGUST EMAIL BILLING		124.00	08/17/21
210836	08/17/21	TRI-STATE TECHNICAL	34116, 34008, PC TROUBLESHOOTING		522.50	08/17/21
210841	08/17/21	TRI-STATE TECHNICAL	33962, ADMIN PC ISSUES		95.00	08/17/21
Total for	Appropriation Control Data Processing - O/E			3,519.46		
01-2010-20-1402-002 Appropriation Control Data Processing - O/E Copy Machine Lease						
210817	08/05/21	MUNICIPAL CAPITAL FINANCE	3063030821, JULY 2021 COPIER LEASE		987.75	08/17/21
Total for	Appropriation Control Data Processing - O/E			987.75		
Department Total: Appropriation Control Data Processing - O/E				4,507.21		

Bills List

BOROUGH OF BOGOTA

08/17/21 04:28:19 PM

PO Number	Po Date	Vendor	Description		Amount	Paid Date
01-2010-20-1451-000 Appropriation Control Revenue Administration - S&W Salary &						
210728	07/14/21	BOROUGH OF BOGOTA	2021-07-15 PR		535.50	07/14/21
210740	07/27/21	BOROUGH OF BOGOTA	2021-07-30 PR		433.50	07/27/21
210821	08/11/21	BOROUGH OF BOGOTA	2021-08-13 PR		433.50	08/11/21
Total for	Appropriation Control Revenue Administration -			1,402.50		
Department Total: Appropriation Control Revenue Administration -				1,402.50		
01-2010-20-1452-000 Appropriation Control Revenue Administration - O/E Other						
210099	02/03/21	BATTAGLIA ASSOCIATES, LLC.	BO-2021-07 JUL FINANCIAL & TAX		5,916.00	08/17/21
Total for	Appropriation Control Revenue Administration -			5,916.00		
Department Total: Appropriation Control Revenue Administration -				5,916.00		
01-2010-20-1501-000 Appropriation Control Tax Assessment - S&W Salary & Wages						
210728	07/14/21	BOROUGH OF BOGOTA	2021-07-15 PR		855.97	07/14/21
210740	07/27/21	BOROUGH OF BOGOTA	2021-07-30 PR		692.88	07/27/21
210821	08/11/21	BOROUGH OF BOGOTA	2021-08-13 PR		692.88	08/11/21
Total for	Appropriation Control Tax Assessment - S&W			2,241.73		
Department Total: Appropriation Control Tax Assessment - S&W				2,241.73		
01-2010-20-1552-001 Appropriation Control Legal Services - O/E Retainer - Municipal						
210838	08/17/21	BOGGIA & BOGGIA, LLC	AUGUST 2021 RETAINER		6,500.00	08/17/21
Total for	Appropriation Control Legal Services - O/E			6,500.00		
01-2010-20-1552-002 Appropriation Control Legal Services - O/E Other Matters						
210744	07/29/21	BOGGIA & BOGGIA, LLC	PROF SRVCS RENDERED THROUGH		2,652.00	08/17/21
Total for	Appropriation Control Legal Services - O/E			2,652.00		
01-2010-20-1552-003 Appropriation Control Legal Services - O/E Bond Counsel						
210761	08/03/21	ROGUT McCARTHY LLC	VOID DUPLICATE		0.00	08/17/21
Total for	Appropriation Control Legal Services - O/E			0.00		
Department Total: Appropriation Control Legal Services - O/E				9,152.00		
01-2010-20-1652-000 Appropriation Control Engineering Services - O/E Other Expenses						
210832	08/17/21	COSTA ENGINEERING	20934, ENGINEERING SRVCS 5/10 & 7/7		675.00	08/17/21
210703	07/13/21	NEGLIA ENGINEERING	PROF SRVCS THROUGH 05/01/2021		594.00	08/17/21
210745	07/29/21	NEGLIA ENGINEERING	PROF SRVCS RENDERED THROUGH		3,303.27	08/17/21

Bills List

BOROUGH OF BOGOTA

08/17/21 04:28:19 PM

PO Number	Po Date	Vendor	Description		Amount	Paid Date
Total for	Appropriation Control Engineering Services -			4,572.27		
Department Total: Appropriation Control Engineering Services -				4,572.27		
01-2010-21-1801-000 Appropriation Control Planning/Zoning Board - S&W Salaries &						
210728	07/14/21	BOROUGH OF BOGOTA	2021-07-15 PR		19.08	07/14/21
Total for	Appropriation Control Planning/Zoning Board -			19.08		
Department Total: Appropriation Control Planning/Zoning Board -				19.08		
01-2010-22-1951-000 Appropriation Control Construction Code - S&W Salary & Wages						
210728	07/14/21	BOROUGH OF BOGOTA	2021-07-15 PR		4,537.95	07/14/21
210740	07/27/21	BOROUGH OF BOGOTA	2021-07-30 PR		3,457.70	07/27/21
210821	08/11/21	BOROUGH OF BOGOTA	2021-08-13 PR		7,290.78	08/11/21
Total for	Appropriation Control Construction Code - S&W			15,286.43		
Department Total: Appropriation Control Construction Code - S&W				15,286.43		
01-2010-22-1952-000 Appropriation Control Construction Code - O/E Other Expenses						
210804	08/09/21	STAPLES	INV3481204951,3481204957,3480278065		298.80	08/17/21
Total for	Appropriation Control Construction Code - O/E			298.80		
Department Total: Appropriation Control Construction Code - O/E				298.80		
01-2010-22-2001-000 Appropriation Control Property Maintenance - S&W Salary & Wages						
210728	07/14/21	BOROUGH OF BOGOTA	2021-07-15 PR		2,907.50	07/14/21
210740	07/27/21	BOROUGH OF BOGOTA	2021-07-30 PR		2,017.50	07/27/21
210821	08/11/21	BOROUGH OF BOGOTA	2021-08-13 PR		1,282.50	08/11/21
Total for	Appropriation Control Property Maintenance -			6,207.50		
Department Total: Appropriation Control Property Maintenance -				6,207.50		
01-2010-23-2202-003 Appropriation Control Group Insurance - O/E Dental						
210828	08/17/21	DELTA DENTAL PLAN OF N.J.,	EMPLOYEE DENTAL COVERAGE SEPTEMBER		3,015.71	08/17/21
Total for	Appropriation Control Group Insurance - O/E			3,015.71		
01-2010-23-2202-004 Appropriation Control Group Insurance - O/E Life/AD&D						
210731	07/20/21	OTTERSTEDT INSURANCE	INV #28644; FOOTBALL CLINIC		116.00	08/17/21
210738	07/27/21	RELIANCE STANDARD LIFE	AUGUST EMPLOYEE INSURANCE COVERAGE		300.74	07/27/21
Total for	Appropriation Control Group Insurance - O/E			416.74		
01-2010-23-2202-092 Appropriation Control Group Insurance - O/E Medical Insurance						

Bills List

BOROUGH OF BOGOTA

08/17/21 04:28:19 PM

PO Number	Po Date	Vendor	Description		Amount	Paid Date
210747	07/29/21	SHBP - STATE PENSIONS &	EE HEALTH BENEFITS AUGUST 2021		59,264.22	07/29/21
Total for		**Appropriation Control Group Insurance - O/E**		**59,264.22**		
01-2010-23-2202-094		Appropriation Control Group Insurance - O/E Disability				
210739	07/27/21	UNUM LIFE INSURANCE CO OF	JULY & AUGUST 2021 DISABILITY		2,490.60	07/27/21
Total for		**Appropriation Control Group Insurance - O/E**		**2,490.60**		
Department Total:		**Appropriation Control Group Insurance - O/E**		**65,187.27**		
01-2010-25-2401-000		Appropriation Control Police - S&W Regular				
210728	07/14/21	BOROUGH OF BOGOTA	2021-07-15 PR		58,058.18	07/14/21
210740	07/27/21	BOROUGH OF BOGOTA	2021-07-30 PR		58,891.54	07/27/21
210821	08/11/21	BOROUGH OF BOGOTA	2021-08-13 PR		58,474.86	08/11/21
Total for		**Appropriation Control Police - S&W Regular**		**175,424.58**		
01-2010-25-2401-002		Appropriation Control Police - S&W Overtime				
210728	07/14/21	BOROUGH OF BOGOTA	2021-07-15 PR		4,342.49	07/14/21
210740	07/27/21	BOROUGH OF BOGOTA	2021-07-30 PR		8,415.51	07/27/21
210821	08/11/21	BOROUGH OF BOGOTA	2021-08-13 PR		11,252.60	08/11/21
Total for		**Appropriation Control Police - S&W Overtime**		**24,010.60**		
Department Total:		**Appropriation Control Police - S&W**		**199,435.18**		
01-2010-25-2402-002		Appropriation Control Police - O/E Equipment Maintenance				
210834	08/17/21	EXTEL COMMUNICATIONS	59086, POLICE PHONE SERVICE		185.00	08/17/21
Total for		**Appropriation Control Police - O/E Equipment**		**185.00**		
01-2010-25-2402-007		Appropriation Control Police - O/E Vehicle Maintenance				
210783	08/09/21	TOM'S SERVICE CENTER	INVOICE #38652, LF FR POWER WINDOW		351.46	08/17/21
210785	08/09/21	TOM'S SERVICE CENTER	INVOICE #38757, VEH 44, ENGINE MT &		267.43	08/17/21
210786	08/09/21	TOM'S SERVICE CENTER	INVOICE # 38712, VEH # 48, BELT		430.00	08/17/21
210787	08/09/21	TOM'S SERVICE CENTER	INVOICE # 38774, VEH#42, A/C		147.33	08/17/21
210789	08/09/21	TOM'S SERVICE CENTER	INVOICE #38733, VEH#48, TIRE ROD		478.75	08/17/21
210790	08/09/21	TOM'S SERVICE CENTER	INVOICE #38724, VEH#42, ENGINE MT,		1,753.78	08/17/21
210791	08/09/21	TOM'S SERVICE CENTER	INV#38763, VEH#48, HEADLIGHT MODULE		887.26	08/17/21
Total for		**Appropriation Control Police - O/E Vehicle**		**4,316.01**		
01-2010-25-2402-008		Appropriation Control Police - O/E Special Services				

Bills List

BOROUGH OF BOGOTA

08/17/21 04:28:19 PM

PO Number	Po Date	Vendor	Description		Amount	Paid Date
210794	08/09/21	INST.FOR FORENSIC	INV # 15601, PSYCH EXAM FOR MICHAEL		500.00	08/17/21
210795	08/09/21	INST.FOR FORENSIC	INV #15601, PSYCH EXAM FOR JOSEPH		500.00	08/17/21
Total for		**Appropriation Control Police - O/E Special**		**1,000.00**		
Department Total:		**Appropriation Control Police - O/E**		**5,501.01**		
01-2010-25-2411-000		Appropriation Control Police Clerical - S&W Salary & Wages				
210728	07/14/21	BOROUGH OF BOGOTA	2021-07-15 PR		2,008.07	07/14/21
210740	07/27/21	BOROUGH OF BOGOTA	2021-07-30 PR		1,625.63	07/27/21
210821	08/11/21	BOROUGH OF BOGOTA	2021-08-13 PR		1,625.63	08/11/21
Total for		**Appropriation Control Police Clerical - S&W**		**5,259.33**		
Department Total:		**Appropriation Control Police Clerical - S&W**		**5,259.33**		
01-2010-25-2421-000		Appropriation Control Crossing Guards - S&W Salary & Wages				
210728	07/14/21	BOROUGH OF BOGOTA	2021-07-15 PR		1,570.71	07/14/21
Total for		**Appropriation Control Crossing Guards - S&W**		**1,570.71**		
Department Total:		**Appropriation Control Crossing Guards - S&W**		**1,570.71**		
01-2010-25-2501-000		Appropriation Control Police Dispatching/911 - S&W Salary &				
210728	07/14/21	BOROUGH OF BOGOTA	2021-07-15 PR		10,356.37	07/14/21
210740	07/27/21	BOROUGH OF BOGOTA	2021-07-30 PR		8,246.08	07/27/21
210821	08/11/21	BOROUGH OF BOGOTA	2021-08-13 PR		8,060.45	08/11/21
Total for		**Appropriation Control Police Dispatching/911 -**		**26,662.90**		
Department Total:		**Appropriation Control Police Dispatching/911 -**		**26,662.90**		
01-2010-25-2552-001		Appropriation Control Fire - O/E Other Expenses				
210814	08/10/21	BOGOTA FIRE DEPT	REIMBURSEMENT FOR MISC. EQUIPMENT		925.00	08/17/21
210629	06/21/21	D & V DESIGNS, LLC	INVOICE # 2499, LETTERING FOR		700.00	08/17/21
210798	08/09/21	FERRARA FIRE APPARATUS,	NRO#13934, REPAIR TO AERIAL CONTROL		275.00	08/17/21
210799	08/09/21	TOM'S SERVICE CENTER	INV# 38835, BATTERIES FOR SP OPS		390.62	08/17/21
Total for		**Appropriation Control Fire - O/E Other**		**2,290.62**		
01-2010-25-2552-003		Appropriation Control Fire - O/E Contribution				
210717	07/13/21	BOGOTA ENGINE CO #3	AID TO VOLUNTEER FIRE COMPANIES		2,500.00	08/17/21
210715	07/13/21	BOGOTA ENGINE CO. #1	AID TO VOLUNTEER FIRE COMPANIES		2,500.00	08/17/21
210718	07/13/21	BOGOTA HOOK AND LADDER CO.	AID TO VOLUNTEER FIRE COMPANIES		2,500.00	08/17/21

Bills List

BOROUGH OF BOGOTA

08/17/21 04:28:19 PM

PO Number	Po Date	Vendor	Description		Amount	Paid Date
210716	07/13/21	BOGOTA HOSE CO. #2	AID TO VOLUNTEER FIRE COMPANIES		2,500.00	08/17/21
Total for	Appropriation Control Fire - O/E Contribution			10,000.00		
Department Total: Appropriation Control Fire - O/E				12,290.62		
01-2010-25-2602-001	Appropriation Control Rescue Squad - O/E Other Expenses					
210687	07/08/21	WAYNE SORGE	PARTS FOR RESCUE 460 AND 461		546.09	08/17/21
Total for	Appropriation Control Rescue Squad - O/E Other			546.09		
Department Total: Appropriation Control Rescue Squad - O/E				546.09		
01-2010-25-2651-000	Appropriation Control Uniform Fire Safety - S&W Salary & Wages					
210728	07/14/21	BOROUGH OF BOGOTA	2021-07-15 PR		1,597.23	07/14/21
210740	07/27/21	BOROUGH OF BOGOTA	2021-07-30 PR		1,994.72	07/27/21
210821	08/11/21	BOROUGH OF BOGOTA	2021-08-13 PR		2,379.64	08/11/21
Total for	Appropriation Control Uniform Fire Safety -			5,971.59		
Department Total: Appropriation Control Uniform Fire Safety -				5,971.59		
01-2010-26-2901-000	Appropriation Control DPW - S&W Regular					
210728	07/14/21	BOROUGH OF BOGOTA	2021-07-15 PR		24,486.53	07/14/21
210740	07/27/21	BOROUGH OF BOGOTA	2021-07-30 PR		25,307.58	07/27/21
210821	08/11/21	BOROUGH OF BOGOTA	2021-08-13 PR		24,394.01	08/11/21
Total for	Appropriation Control DPW - S&W Regular			74,188.12		
01-2010-26-2901-002	Appropriation Control DPW - S&W Overtime					
210728	07/14/21	BOROUGH OF BOGOTA	2021-07-15 PR		983.87	07/14/21
210821	08/11/21	BOROUGH OF BOGOTA	2021-08-13 PR		44.72	08/11/21
Total for	Appropriation Control DPW - S&W Overtime			1,028.59		
Department Total: Appropriation Control DPW - S&W				75,216.71		
01-2010-26-2902-003	Appropriation Control DPW - O/E Vehicle Repairs & Maintenance					
210706	07/13/21	46 TRUCK REPAIR INC.	WORK # 000055524		2,210.80	08/17/21
210750	08/02/21	46 TRUCK REPAIR INC.	WORK ORDER # 000055629, 000055641,		2,040.00	08/17/21
210754	08/02/21	46 TRUCK REPAIR INC.	WORK # 000055572, FIX JAMMED		1,244.00	08/17/21
210824	08/12/21	46 TRUCK REPAIR INC.	WO#		2,858.82	08/17/21
210792	08/09/21	SUPERIOR DISTRIBUTORS	211830125, MIRRORS/TAIL LIGHTS		192.07	08/17/21
210758	08/02/21	TIMMERMAN EQUIPMENT CO.	INVOICE # 0223987-IN, SWEEPER		1,365.55	08/17/21

Bills List

BOROUGH OF BOGOTA

08/17/21 04:28:19 PM

PO Number	Po Date	Vendor	Description		Amount	Paid Date
210708	07/13/21	UNITED MOTOR PARTS	INVOICE # 2264294 & 2263543		444.86	08/17/21
Total for	Appropriation Control DPW - O/E Vehicle			10,356.10		
01-2010-26-2902-008	Appropriation Control DPW - O/E Tools & Equipment					
210767	08/03/21	AGL WELDING SUPPLY CO, INC	INVOICE # 10048257, 02 & ACETYLENCE		53.20	08/17/21
210774	08/09/21	MATERA'S NURSERY	INVOICE # 340061, W-WHACKER HEADS &		298.70	08/17/21
Total for	Appropriation Control DPW - O/E Tools &			351.90		
Department Total: Appropriation Control DPW - O/E				10,708.00		
01-2010-26-3001-000	Appropriation Control Shade Tree - S&W Salary & Wages					
210728	07/14/21	BOROUGH OF BOGOTA	2021-07-15 PR		112.75	07/14/21
210740	07/27/21	BOROUGH OF BOGOTA	2021-07-30 PR		112.75	07/27/21
210821	08/11/21	BOROUGH OF BOGOTA	2021-08-13 PR		112.75	08/11/21
Total for	Appropriation Control Shade Tree - S&W Salary			338.25		
Department Total: Appropriation Control Shade Tree - S&W				338.25		
01-2010-26-3002-000	Appropriation Control Shade Tree - O/E Other Expenses					
210737	07/21/21	HARDWOOD TREE SERVICE	INVOICE # 35835		6,650.00	08/17/21
210751	08/02/21	HARDWOOD TREE SERVICE	INVOICE # 36433, PRUNED 2 WILLOWS @		950.00	08/17/21
210755	08/02/21	HARDWOOD TREE SERVICE	INVOICE # 36623, REMOVED 3 FISCHER		8,450.00	08/17/21
210801	08/09/21	HARDWOOD TREE SERVICE	INV# 36487, REMOVED FALLEN LIMB AT		550.00	08/17/21
Total for	Appropriation Control Shade Tree - O/E Other			16,600.00		
Department Total: Appropriation Control Shade Tree - O/E				16,600.00		
01-2010-26-3052-001	Appropriation Control Solid Waste Collection - O/E Contract					
210837	08/17/21	SUBURBAN DISPOSAL INC	7871, AUG 2021 SOLID WASTE		31,800.00	08/17/21
Total for	Appropriation Control Solid Waste Collection -			31,800.00		
Department Total: Appropriation Control Solid Waste Collection -				31,800.00		
01-2010-26-3102-001	Appropriation Control Buildings & Grounds - O/E Contract -					
210753	08/02/21	MATERA'S NURSERY	INVOICE # 339915, BLADE FOR LAWN		19.95	08/17/21
210759	08/02/21	MATERA'S NURSERY	INVOICE # 338330, BAR & CHAIN OIL,		349.35	08/17/21
Total for	Appropriation Control Buildings & Grounds -			369.30		
01-2010-26-3102-002	Appropriation Control Buildings & Grounds - O/E Contract -					
210641	06/22/21	JERSEY ELEVATOR CO, INC	254946, JUNE 2021 ELEVATOR MAINT.		164.15	08/17/21

Bills List

BOROUGH OF BOGOTA

08/17/21 04:28:19 PM

PO Number	Po Date	Vendor	Description	Amount	Paid Date
210839	08/17/21	JERSEY ELEVATOR CO, INC	256553, 258129, JUL & AUG ELEVATOR	328.30	08/17/21
210730	07/20/21	STATE OF NEW JERSEY	2021 ANNUAL ELEVATOR INSPECTION FEE	258.00	07/20/21
Total for	Appropriation Control Buildings & Grounds -		750.45		
01-2010-26-3102-003	Appropriation Control Buildings & Grounds - O/E Other Expenses				
210685	07/08/21	ALLAN BRITEWAY	INVOICE # 16205, REPAIR TO	534.22	08/17/21
210683	07/08/21	BERGEN FENCE	INVOICE # 54720, FENCE AT SWIM CLUB	7,998.00	08/17/21
210683	07/08/21	BERGEN FENCE	INVOICE # 54720, FENCE AT SWIM CLUB	-7,998.00	08/17/21
210757	08/02/21	BRAEN STONE	INVOICE # 119518, F.A.B.C. TOP	58.00	08/17/21
210109	02/04/21	COOPER PEST SOLUTIONS	FEB-AUG 2021 BORO HALL PEST CONTROL	0.00	08/17/21
210109	02/04/21	COOPER PEST SOLUTIONS	FEB-AUG 2021 BORO HALL PEST CONTROL	1,400.00	08/17/21
210109	02/04/21	COOPER PEST SOLUTIONS	FEB-AUG 2021 DPW PEST CONTROL	0.00	08/17/21
210109	02/04/21	COOPER PEST SOLUTIONS	FEB-AUG 2021 DPW PEST CONTROL	752.50	08/17/21
210756	08/02/21	HOME DEPOT CREDIT	INVOICE # 6014725 & 6084319	314.10	08/17/21
210825	08/16/21	HOME DEPOT CREDIT	INV # 7524780, MOP HEADS & CAUTION	47.88	08/17/21
210771	08/09/21	MATERA'S NURSERY	INVOICE # 9375331, SERVICE OF 48"	314.75	08/17/21
210666	07/02/21	NEW JERSEY DOOR WORKS	INVOICE # 138940, REPAIR ENGINE #3	2,840.00	08/17/21
210773	08/09/21	QUALITY COOLING CORP	INVOICE # 2021-043, 3 NEW WALL	695.00	08/17/21
210707	07/13/21	TRAFFIC SAFETY & EQUIPMENT	INVOICE # 221402, WHITE & YELLOW	810.00	08/17/21
210831	08/17/21	VERIZON	ACCOUNT #250-718-378-0001-23 AUG	44.55	08/17/21
210820	08/12/21	VERIZON	ACCOUNT #250-718-378-0001-23 JULY	39.50	08/12/21
Total for	Appropriation Control Buildings & Grounds -		7,850.50		
Department Total:	Appropriation Control Buildings & Grounds -		8,970.25		
01-2010-27-3301-000	Appropriation Control Board of Health - S&W Salary & Wages				
210728	07/14/21	BOROUGH OF BOGOTA	2021-07-15 PR	112.75	07/14/21
210740	07/27/21	BOROUGH OF BOGOTA	2021-07-30 PR	112.75	07/27/21
210821	08/11/21	BOROUGH OF BOGOTA	2021-08-13 PR	112.75	08/11/21
Total for	Appropriation Control Board of Health - S&W		338.25		
Department Total:	Appropriation Control Board of Health - S&W		338.25		
01-2010-27-3302-001	Appropriation Control Board of Health - O/E Contract				
210842	08/17/21	MID-BERGEN REGIONAL HEALTH	PUBLIC HEALTH OFFICER 2021 Q2 & Q3	0.00	08/17/21

Bills List

BOROUGH OF BOGOTA

08/17/21 04:28:19 PM

PO Number	Po Date	Vendor	Description	Amount	Paid Date
210842	08/17/21	MID-BERGEN REGIONAL HEALTH	PUBLIC HEALTH OFFICER 2021 Q2 & Q3	16,993.00	08/17/21
Total for	Appropriation Control Board of Health - O/E		16,993.00		
Department Total:	Appropriation Control Board of Health - O/E		16,993.00		
01-2010-27-3650-001	Appropriation Control Seniors - S&W Salaries & Wages				
210728	07/14/21	BOROUGH OF BOGOTA	2021-07-15 PR	17.00	07/14/21
Total for	Appropriation Control Seniors - S&W Salaries &		17.00		
Department Total:	Appropriation Control Seniors - S&W		17.00		
01-2010-28-3701-000	Appropriation Control Recreation Services - S&W Regular				
210728	07/14/21	BOROUGH OF BOGOTA	2021-07-15 PR	3,221.21	07/14/21
210740	07/27/21	BOROUGH OF BOGOTA	2021-07-30 PR	1,930.95	07/27/21
210821	08/11/21	BOROUGH OF BOGOTA	2021-08-13 PR	1,930.95	08/11/21
Total for	Appropriation Control Recreation Services -		7,083.11		
01-2010-28-3701-002	Appropriation Control Recreation Services - S&W Counselors				
210728	07/14/21	BOROUGH OF BOGOTA	2021-07-15 PR	686.23	07/14/21
210740	07/27/21	BOROUGH OF BOGOTA	2021-07-30 PR	484.32	07/27/21
210821	08/11/21	BOROUGH OF BOGOTA	2021-08-13 PR	484.32	08/11/21
Total for	Appropriation Control Recreation Services -		1,654.87		
Department Total:	Appropriation Control Recreation Services -		8,737.98		
01-2010-28-3702-001	Appropriation Control Recreation Services - O/E Other Expenses				
210788	08/09/21	BOUNCE PARTY MANIA	INVOICE #56656, OUTDOOR MOVIE THT	650.00	08/17/21
210840	08/17/21	COOPER PEST SOLUTIONS	JULY 2021 PEST CONTROL REC	51.50	08/17/21
210782	08/09/21	COSTCO BUSINESS CENTER	BOROUGH SUPPLIES ON 7/14 & 8/2	1,094.47	08/17/21
210762	08/03/21	MAIN LOCK SHOP	0178363-IN; KEYS & RINGS	36.00	08/17/21
210778	08/09/21	OTTERSTEDT INSURANCE	INVOICE # 28644, INSURANCE FOR	116.00	08/17/21
210777	08/09/21	QUILL CORPORATION	INVOICE # 18098724, INK FOR REC	194.96	08/17/21
210779	08/09/21	SAL STAMILLA	JULY 6,8,13,15,20,22,27,29 T&C	120.00	08/17/21
210781	08/09/21	SIGN A RAMA, USA	INVOICE # INV-71046, REPAIR GRAD	150.00	08/17/21
210775	08/09/21	TOM'S SERVICE CENTER	INVOICE # 38759, SERVICE & REPAIRS	1,667.95	08/17/21
210760	08/02/21	UNITED MOTOR PARTS	INVOICE # 2079599, BATTERY FOR	120.00	08/17/21
210776	08/09/21	UNITED SITE SERVICES	INVOICE # 000625, 7/28/21 PORTA	493.20	08/17/21

PO Number	Po Date	Vendor	Description		Amount	Paid Date
Total for	Appropriation Control Recreation Services -			4,694.08		
01-2010-28-3702-002	Appropriation Control Recreation Services - O/E Senior Citizens					
210780	08/09/21	INSERRA SUPERMARKETS	SR SHOPPING JULY 8, 13, 15, 22, 29		799.80	08/17/21
Total for	Appropriation Control Recreation Services -			799.80		
Department Total: Appropriation Control Recreation Services -				5,493.88		
01-2010-28-3703-001	Appropriation Control Celebration of Public Events Celebration					
210802	08/09/21	RAMSEY GRAPHICS & PRINTING	567-4, INVITATIONS VOLUNTEER DINNER		303.00	08/17/21
210334	04/06/21	THE BROWNSTONE	VOLUNTEER DINNER 2021		500.00	08/03/21
Total for	Appropriation Control Celebration of Public			803.00		
Department Total: Appropriation Control Celebration of Public				803.00		
01-2010-29-3901-000	Appropriation Control Free Public Library - 1/3 mil S&W					
210728	07/14/21	BOROUGH OF BOGOTA	2021-07-15 PR		8,652.52	07/14/21
210740	07/27/21	BOROUGH OF BOGOTA	2021-07-30 PR		8,488.03	07/27/21
210821	08/11/21	BOROUGH OF BOGOTA	2021-08-13 PR		8,450.53	08/11/21
Total for	Appropriation Control Free Public Library -			25,591.08		
Department Total: Appropriation Control Free Public Library -				25,591.08		
01-2010-31-4402-001	Appropriation Control Telephone SPECTROTEL #320604					
210829	08/17/21	METROPOLITAN-TELECOMMUNICA	AUGUST 2021 PHONE CHARGES		1,782.75	08/17/21
Total for	Appropriation Control Telephone SPECTROTEL			1,782.75		
01-2010-31-4402-012	Appropriation Control Telephone CABLEVISION - REC BLDG					
210822	08/12/21	OPTIMUM	JULY/AUGUST 2021 CABLE/ISP CHARGES		346.88	08/12/21
Total for	Appropriation Control Telephone CABLEVISION -			346.88		
01-2010-31-4402-014	Appropriation Control Telephone CABLE TV & ISP - FD CO#1 ENGIN					
210822	08/12/21	OPTIMUM	JULY/AUGUST 2021 CABLE/ISP CHARGES		256.86	08/12/21
Total for	Appropriation Control Telephone CABLE TV & ISP			256.86		
01-2010-31-4402-016	Appropriation Control Telephone 07870-061598-01-0					
210822	08/12/21	OPTIMUM	JULY/AUGUST 2021 CABLE/ISP CHARGES		474.16	08/12/21
Total for	Appropriation Control Telephone			474.16		
01-2010-31-4402-017	Appropriation Control Telephone CABLE TV & ISP - OEM					
210822	08/12/21	OPTIMUM	JULY/AUGUST 2021 CABLE/ISP CHARGES		188.60	08/12/21

Bills List BOROUGH OF BOGOTA

08/17/21 04:28:19 PM

PO Number	Po Date	Vendor	Description		Amount	Paid Date
Total for	Appropriation Control Telephone CABLE TV & ISP			188.60		
01-2010-31-4402-018	Appropriation Control Telephone CABLE TV & ISP - SQUAD RESCUE					
210822	08/12/21	OPTIMUM	JULY/AUGUST 2021 CABLE/ISP CHARGES		199.78	08/12/21
Total for	Appropriation Control Telephone CABLE TV & ISP			199.78		
01-2010-31-4402-020	Appropriation Control Telephone CABLE TV & ISP - BORO HALL					
210822	08/12/21	OPTIMUM	JULY/AUGUST 2021 CABLE/ISP CHARGES		446.88	08/12/21
Total for	Appropriation Control Telephone CABLE TV & ISP			446.88		
01-2010-31-4402-021	Appropriation Control Telephone 07870-495094-01-4					
210822	08/12/21	OPTIMUM	JULY/AUGUST 2021 CABLE/ISP CHARGES		0.00	08/12/21
210822	08/12/21	OPTIMUM	JULY/AUGUST 2021 CABLE/ISP CHARGES		548.38	08/12/21
Total for	Appropriation Control Telephone			548.38		
01-2010-31-4402-022	Appropriation Control Telephone VERIZON - ELEVATOR LINE					
210823	08/12/21	VERIZON	JULY/AUGUST 2021 ELEVATOR LINE		79.08	08/12/21
Total for	Appropriation Control Telephone VERIZON -			79.08		
Department Total: Appropriation Control Telephone				4,323.37		
01-2010-31-4602-001	Appropriation Control Gasoline DPW					
210764	08/03/21	VILLAGE OF RIDGEFIELD PARK	JULY 2021 FUEL CHARGES		2,113.27	08/17/21
Total for	Appropriation Control Gasoline DPW			2,113.27		
01-2010-31-4602-002	Appropriation Control Gasoline Police					
210764	08/03/21	VILLAGE OF RIDGEFIELD PARK	JULY 2021 FUEL CHARGES		1,991.54	08/17/21
Total for	Appropriation Control Gasoline Police			1,991.54		
01-2010-31-4602-003	Appropriation Control Gasoline Recreation					
210764	08/03/21	VILLAGE OF RIDGEFIELD PARK	JULY 2021 FUEL CHARGES		55.02	08/17/21
Total for	Appropriation Control Gasoline Recreation			55.02		
01-2010-31-4602-004	Appropriation Control Gasoline Rescue					
210764	08/03/21	VILLAGE OF RIDGEFIELD PARK	JULY 2021 FUEL CHARGES		44.94	08/17/21
Total for	Appropriation Control Gasoline Rescue			44.94		
01-2010-31-4602-005	Appropriation Control Gasoline Fire Department					
210764	08/03/21	VILLAGE OF RIDGEFIELD PARK	JULY 2021 FUEL CHARGES		421.86	08/17/21
Total for	Appropriation Control Gasoline Fire Department			421.86		

Bills List

BOROUGH OF BOGOTA

08/17/21 04:28:19 PM

PO Number	Po Date	Vendor	Description		Amount	Paid Date
Department Total: Appropriation Control Gasoline				4,626.63		
01-2010-32-4652-001 Appropriation Control Solid Waste Disposal BCUA Type 10 Dump						
210741	07/29/21	BCUA [SEWER CHARGES]	INVOICE # 1041; JUNE 2021 SOLID		30,278.64	08/17/21
Total for Appropriation Control Solid Waste Disposal				30,278.64		
01-2010-32-4652-002 Appropriation Control Solid Waste Disposal Miscellaneous						
210705	07/13/21	ATLANTIC COAST FIBERS	INVOICE # INV116353, MX COM		337.56	08/17/21
210704	07/13/21	ENVIRONMENTAL RENEWAL, LLC	INVOICE # 310478 & 310479 MX YRD		750.00	08/17/21
210736	07/21/21	ENVIRONMENTAL RENEWAL, LLC	INVOICE # 310641 & 310642		775.00	08/17/21
210749	08/02/21	ENVIRONMENTAL RENEWAL, LLC	INVOICE # 310804 & 310805, MX YARD		775.00	08/17/21
210766	08/03/21	ENVIRONMENTAL RENEWAL, LLC	INVOICE # 310968, COMPT MX YARD		800.00	08/17/21
210772	08/09/21	ENVIRONMENTAL RENEWAL, LLC	INVOICE # 308941, CMPT MX YARD		500.00	08/17/21
210805	08/10/21	ENVIRONMENTAL RENEWAL, LLC	INV # 311118 & 311120, CMPT MX YARD		775.00	08/17/21
210826	08/16/21	ENVIRONMENTAL RENEWAL, LLC	INV # 311226, CMPT MX YARD WASTE		325.00	08/17/21
210827	08/16/21	ENVIRONMENTAL RENEWAL, LLC	311275, 31176, COMPACTED MIXED		875.00	08/17/21
Total for Appropriation Control Solid Waste Disposal				5,912.56		
Department Total: Appropriation Control Solid Waste Disposal				36,191.20		
01-2010-36-4722-000 Appropriation Control Social Security System						
210728	07/14/21	BOROUGH OF BOGOTA	2021-07-15 PR		0.00	07/14/21
210728	07/14/21	BOROUGH OF BOGOTA	2021-07-15 PR		7,088.06	07/14/21
210740	07/27/21	BOROUGH OF BOGOTA	2021-07-30 PR		0.00	07/27/21
210740	07/27/21	BOROUGH OF BOGOTA	2021-07-30 PR		6,171.67	07/27/21
210821	08/11/21	BOROUGH OF BOGOTA	2021-08-13 PR		0.00	08/11/21
210821	08/11/21	BOROUGH OF BOGOTA	2021-08-13 PR		6,461.28	08/11/21
Total for Appropriation Control Social Security System				19,721.01		
Department Total: Appropriation Control Social Security System				19,721.01		
01-2010-42-4901-000 Appropriation Control Municipal Court - S&W						
210728	07/14/21	BOROUGH OF BOGOTA	2021-07-15 PR		1,624.87	07/14/21
210740	07/27/21	BOROUGH OF BOGOTA	2021-07-30 PR		1,315.51	07/27/21
210821	08/11/21	BOROUGH OF BOGOTA	2021-08-13 PR		1,315.51	08/11/21
Total for Appropriation Control Municipal Court - S&W				4,255.89		

Bills List

BOROUGH OF BOGOTA

08/17/21 04:28:19 PM

PO Number	Po Date	Vendor	Description		Amount	Paid Date
Department Total: Appropriation Control Municipal Court - S&W				4,255.89		
01-2030-20-1652-000 APPROPRIATION RESERVES Engineering Services - O/E Other Expenses						
210723	07/13/21	NEGLIA ENGINEERING	2000074, 2000077, PROF SRVCS GEN		1,870.00	08/17/21
210724	07/13/21	NEGLIA ENGINEERING	2003805, PROF SRVCS GEN ENGINEERING		377.50	08/17/21
Total for APPROPRIATION RESERVES Engineering Services -				2,247.50		
Department Total: APPROPRIATION RESERVES Engineering Services -				2,247.50		
01-2030-22-1952-000 APPROPRIATION RESERVES Construction Code - O/E Other Expenses						
210702	07/13/21	MUNICIPAL INFORMATION	INV #109131, 109132, 109342,		1,800.00	08/17/21
Total for APPROPRIATION RESERVES Construction Code - O/E				1,800.00		
Department Total: APPROPRIATION RESERVES Construction Code - O/E				1,800.00		
01-2030-26-2902-008 APPROPRIATION RESERVES DPW - O/E Tools & Equipment						
201197	09/29/20	GOOSETOWN COMMUNICATIONS	138948, JULY 2021 RADIOS		69.98	08/17/21
Total for APPROPRIATION RESERVES DPW - O/E Tools &				69.98		
Department Total: APPROPRIATION RESERVES DPW - O/E				69.98		
01-2030-28-3703-001 APPROPRIATION RESERVES Celebration of Public Events Celebration						
201238	10/15/20	RILEIGH'S	QUOTE 00002464, 2020 HOLIDAY DECOR		5,993.40	08/17/21
Total for APPROPRIATION RESERVES Celebration of Public				5,993.40		
Department Total: APPROPRIATION RESERVES Celebration of Public				5,993.40		
01-2070-55-0000-000 Local School Taxes Payable Local School Taxes Payable						
210835	08/17/21	BOGOTA BOARD OF EDUCATION	AUGUST SCHOOL TAXES		1,325,189.17	08/17/21
Total for Local School Taxes Payable Local School Taxes				1,325,189.17		
Department Total: Local School Taxes Payable Local School Taxes				1,325,189.17		
01-2080-55-0000-000 County Taxes Payable County Taxes Payable						
210807	08/10/21	COUNTY OF BERGEN, ADMIN &	3RD QTR 2021 COUNTY TAXES		509,493.00	08/10/21
Total for County Taxes Payable County Taxes Payable				509,493.00		
Department Total: County Taxes Payable County Taxes Payable				509,493.00		
01-2110-55-0000-000 County Open Space Tax Payable County Open Space Tax Payable						
210808	08/10/21	COUNTY OPEN SPACE TRUST	3RD QTR 2021 COUNTY OPEN SPACE		21,128.00	08/10/21
Total for County Open Space Tax Payable County Open				21,128.00		
Department Total: County Open Space Tax Payable County Open				21,128.00		

PO Number	Po Date	Vendor	Description		Amount	Paid Date
01-2710-55-0000-001		Due State of NJ Due State of NJ Health Fees				
210768	08/03/21	TREASURER, STATE OF NJ	Q4 MARRIAGE LIC. DUE TO ST -		225.00	08/17/21
210769	08/03/21	TREASURER, STATE OF NJ	Q2 MARRIAGE LIC. DUE TO ST - APRIL		600.00	08/17/21
Total for		Due State of NJ Due State of NJ Health Fees		825.00		
01-2710-55-0000-002		Due State of NJ Due State of NJ DCA Training Fees				
210818	08/12/21	N.J. DEPT OF COMM AFFAIRS	1ST QTR 2021 - STATE PERMIT		434.00	08/17/21
210819	08/12/21	N.J. DEPT OF COMM AFFAIRS	2ND QTR 2021 - STATE PERMIT		6,408.00	08/17/21
Total for		Due State of NJ Due State of NJ DCA Training		6,842.00		
Department Total: Due State of NJ Due State of NJ				7,667.00		
01-2800- - -		RESERVE FOR CREDIT CARD FEES RESERVE FOR CREDIT CARD FEES				
210816	08/05/21	AMERICAN EXPRESS	DEMAND DEBIT - 08/05/2021		126.73	08/05/21
210770	08/02/21	MERCHANT SERVICE FEES	DEMAND DEBIT - 08/02/2021		473.47	08/02/21
Total for		RESERVE FOR CREDIT CARD FEES RESERVE FOR		600.20		
Department Total: RESERVE FOR CREDIT CARD FEES RESERVE FOR				600.20		
04-2150-55-1516-002		Improvement Authorizations 2018 #1516 Resurf - Leonia Ave				
200560	04/29/20	NEGLIA ENGINEERING	PROF SRVCS RENDERED; LEONIA AVE PH		44.24	08/17/21
Total for		Improvement Authorizations 2018 #1516 Resurf -		44.24		
Department Total: Improvement Authorizations 2018 #1516 Resurf -				44.24		
04-2150-55-1522-002		Improvement Authorizations 2019 #1522 Palisade Ave - Phas				
210763	08/03/21	ROGUT McCARTHY LLC	PROF SRVCS 4/1-6/30/21		318.73	08/17/21
Total for		Improvement Authorizations 2019 #1522 Palisade		318.73		
Department Total: Improvement Authorizations 2019 #1522 Palisade				318.73		
04-2150-55-1523-002		Improvment Authorizations 1523 - Var. Cap. Impvts Road				
210763	08/03/21	ROGUT McCARTHY LLC	PROF SRVCS 4/1-6/30/21		178.76	08/17/21
Total for		Improvment Authorizations 1523 - Var. Cap.		178.76		
Department Total: Improvment Authorizations 1523 - Var. Cap.				178.76		
04-2150-55-1528-002		Improvment Authorizations 1528 - Olsen Park Rehabilitati Section				
210726	07/13/21	NEGLIA ENGINEERING	2001096, 2001829, PROF SRVCS OLSEN		5,077.00	08/17/21
210763	08/03/21	ROGUT McCARTHY LLC	PROF SRVCS 4/1-6/30/21		458.70	08/17/21
Total for		Improvment Authorizations 1528 - Olsen Park		5,535.70		

Bills List BOROUGH OF BOGOTA

08/17/21 04:28:19 PM

PO Number	Po Date	Vendor	Description		Amount	Paid Date
Department Total: Improvment Authorizations 1528 - Olsen Park				5,535.70		
04-2150-55-1541-004		Improvment Authorizations 1541 - Var. Cap. Impvts Public				
200561	04/29/20	NEGLIA ENGINEERING	PROF SRVCS RENDERED; PRESTON ST		1,007.75	08/17/21
Total for		Improvment Authorizations 1541 - Var. Cap.		1,007.75		
04-2150-55-1541-005		Improvment Authorizations 1541 - Var. Cap. Impvts Sidewalk				
210763	08/03/21	ROGUT McCARTHY LLC	PROF SRVCS 4/1-6/30/21		318.73	08/17/21
Total for		Improvment Authorizations 1541 - Var. Cap.		318.73		
Department Total: Improvment Authorizations 1541 - Var. Cap.				1,326.48		
04-2150-55-1542-002		Improvment Authorizations 1542 - Pine Street Section 20 Costs				
210745	07/29/21	NEGLIA ENGINEERING	PROF SRVCS RENDERED THROUGH		10,624.23	08/17/21
Total for		Improvment Authorizations 1542 - Pine Street		10,624.23		
Department Total: Improvment Authorizations 1542 - Pine Street				10,624.23		
04-2150-55-1544-002		Improvment Authorizations 1544 - Leonia Ave Ph V Section 20				
200995	08/18/20	NEGLIA ENGINEERING	2002130, PROF. SRVCS LEONIA AVE		1,945.00	08/17/21
210155	02/16/21	NEGLIA ENGINEERING	210065; LEONIA AVE PHASE V		167.50	08/17/21
210725	07/13/21	NEGLIA ENGINEERING	2001095, 2002931, 2003806, PROF		6,114.76	08/17/21
Total for		Improvment Authorizations 1544 - Leonia Ave Ph		8,227.26		
Department Total: Improvment Authorizations 1544 - Leonia Ave Ph				8,227.26		
04-2150-55-1549-001		Improvment Authorizations 1549 - Purchase 31 Fairview FD				
210763	08/03/21	ROGUT McCARTHY LLC	PROF SRVCS 4/1-6/30/21		318.74	08/17/21
Total for		Improvment Authorizations 1549 - Purchase 31		318.74		
Department Total: Improvment Authorizations 1549 - Purchase 31				318.74		
04-2150-55-1560-003		Improvment Authorizations 1560 - Var. Cap. Impvts Sidewalk				
210806	08/10/21	CARRATURA CONSTRUCTION	INV # 2750, SIDEWALK PROG PALISADE		4,950.00	08/17/21
210763	08/03/21	ROGUT McCARTHY LLC	PROF SRVCS 4/1-6/30/21		822.66	08/17/21
Total for		Improvment Authorizations 1560 - Var. Cap.		5,772.66		
04-2150-55-1560-005		Improvment Authorizations 1560 - Var. Cap. Impvts Roads/Sanitary				
210703	07/13/21	NEGLIA ENGINEERING	PROF SRVCS THROUGH 05/01/2021		2,507.20	08/17/21
Total for		Improvment Authorizations 1560 - Var. Cap.		2,507.20		
Department Total: Improvment Authorizations 1560 - Var. Cap.				8,279.86		

Bills List BOROUGH OF BOGOTA

08/17/21 04:28:19 PM

PO Number	Po Date	Vendor	Description		Amount	Paid Date
14-0005-00-0005-062		Outside Police Employment Fees				
210728	07/14/21	BOROUGH OF BOGOTA	2021-07-15 PR		0.00	07/14/21
210728	07/14/21	BOROUGH OF BOGOTA	2021-07-15 PR		13,170.00	07/14/21
210740	07/27/21	BOROUGH OF BOGOTA	2021-07-30 PR		0.00	07/27/21
210740	07/27/21	BOROUGH OF BOGOTA	2021-07-30 PR		8,250.00	07/27/21
210821	08/11/21	BOROUGH OF BOGOTA	2021-08-13 PR		0.00	08/11/21
210821	08/11/21	BOROUGH OF BOGOTA	2021-08-13 PR		13,410.00	08/11/21
Total for		Outside Police Employment Fees		34,830.00		
Department Total: Outside Police Employment Fees				34,830.00		
17-2000-00-1000-		NET PAYROLL NET PAYROLL				
210735	07/20/21	GEORGE HONDROS	STEP INCREASE MISSED 07/15/2021		100.37	07/20/21
210734	07/20/21	JOESPH NAEM	STEP INCREASE MISSED 07/15/2021		89.95	07/20/21
210733	07/20/21	KENNETH O'DONNELL	STEP INCREASE MISSED 07/15/2021		92.16	07/20/21
210732	07/20/21	LEWIS DUENAS	STEP INCREASE MISSED 07/15/2021		90.39	07/20/21
210729	07/15/21	VINCE DIMITRI	2021-07-15 P/R CHECK		697.08	07/15/21
Total for		NET PAYROLL NET PAYROLL		1,069.95		
Department Total: NET PAYROLL NET PAYROLL				1,069.95		

Total Bill List: 2,660,809.43

BOROUGH OF BOGOTA

ORDINANCE NO. 1565

AN ORDINANCE AMENDING CHAPTER 21B OF THE CODE OF BOROUGH OF BOGOTA, ENTITLED "STORMWATER CONTROL"

WHEREAS, Article I of Chapter 21B of the Bogota Code defines and regulates the Borough's stormwater management measures, which are aimed to promote flood control, groundwater recharge and pollution reduction through green infrastructure Best Management Practices (GI BMPs) and nonstructural stormwater management strategies, and;

WHEREAS, Section 7:8 of the New Jersey Administrative Code contains the State of New Jersey's Municipal Stormwater Management Program, which sets forth the stormwater control guidelines that must be administered and followed by each municipality in the State, and;

WHEREAS, the New Jersey Department of Environmental Protection, Division of Water Quality, (hereinafter "NJDEP") had made several amendments to Section 7:8, effective March 2, 2020, and;

WHEREAS, the Borough is required to amend its stormwater management rules to reflect the newly-revised language in the State's Municipal Stormwater Management Program.

NOW, THEREFORE, BE IT ORDAINED by the Mayor and Council of the Borough of Bogota, that Article I of Chapter 21B of the Bogota Code is hereby deleted in its entirety and replaced with the following:

SECTION I: SCOPE AND PURPOSE.

A. Policy Statement

Flood control, groundwater recharge, and pollutant reduction shall be achieved through the use of stormwater management measures, including green infrastructure Best Management Practices (GI BMPs) and nonstructural stormwater management strategies. GI BMPs and low impact development (LID) should be utilized to meet the goal of maintaining natural hydrology to reduce

stormwater runoff volume, reduce erosion, encourage infiltration and groundwater recharge, and reduce pollution. GI BMPs and LID should be developed based upon physical site conditions and the origin, nature and the anticipated quantity, or amount, of potential pollutants. Multiple stormwater management BMPs may be necessary to achieve the established performance standards for water quality, quantity, and groundwater recharge.

B. Purpose

The purpose of this ordinance is to establish minimum stormwater management requirements and controls for "major development," as defined below in Section II herein. Unmitigated stormwaters from areas altered by major development may pose public health and safety threats. This Chapter establishes the administrative mechanisms necessary for the Borough of Bogota to ensure proper stormwater management.

C. Applicability

1. This ordinance shall be applicable to the following major developments:

   a. Non-residential major developments; and
   b. Aspects of residential major developments that are not pre-empted by the Residential Site Improvement Standards at N.J.A.C. 5:21.

2. This ordinance shall also be applicable to all major developments undertaken by the Borough of Bogota.

D. Compatibility with Other Permit and Ordinance Requirements

Development approvals issued pursuant to this ordinance do not relieve the applicant of the responsibility to secure required permits or approvals for activities regulated by any other applicable code, rule, act, or ordinance. In their interpretation and application, the provisions of this ordinance shall be held to be the minimum requirements for the promotion of the public health, safety, and general welfare.

This ordinance is not intended to interfere with, abrogate, or annul any other ordinances, rule or regulation, statute, or other provision of law except that, where any provision of this ordinance imposes restrictions different from those imposed by any other ordinance, rule or regulation, or other provision of law, the more restrictive provisions or higher standards shall control.

SECTION II. DEFINITIONS.

For the purpose of this ordinance, the following terms, phrases, words and their derivations shall have the meanings stated herein, unless their use in the text of this Chapter clearly demonstrates a different meaning. When not inconsistent with the

context, words used in the present tense include the future, words used in the plural number include the singular number, and words used in the singular number include the plural number. The word "shall" is always mandatory and not merely directory. The definitions below are the same as or based on the corresponding definitions in the Stormwater Management Rules at N.J.A.C. 7:8-1.2.

"CAFRA Centers, Cores or Nodes" means those areas with boundaries incorporated by reference or revised by the Department in accordance with N.J.A.C. 7:7-13.16.

"CAFRA Planning Map" means the map used by the Department to identify the location of Coastal Planning Areas, CAFRA centers, CAFRA cores, and CAFRA nodes. The CAFRA Planning Map is available on the Department's Geographic Information System (GIS).

"Community basin" means an infiltration system, sand filter designed to infiltrate, standard constructed wetland, or wet pond, established in accordance with N.J.A.C. 7:8-4.2(c)14, that is designed and constructed in accordance with the New Jersey Stormwater Best Management Practices Manual, or an alternate design, approved in accordance with N.J.A.C. 7:8-5.2(g), for an infiltration system, sand filter designed to infiltrate, standard constructed wetland, or wet pond and that complies with the requirements of this Chapter.

"Compaction" means the increase in soil bulk density.

"Contributory drainage area" means the area from which stormwater runoff drains to a stormwater management measure, not including the area of the stormwater management measure itself.

"Core" means a pedestrian-oriented area of commercial and civic uses serving the surrounding municipality, generally including housing and access to public transportation.

"County review agency" means an agency designated by the County Board of County Commissioners to review municipal stormwater management plans and implementing ordinance(s). The county review agency may either be:

1. A county planning agency or
2. A county water resource association created under N.J.S.A 58:16A-55.5, if the ordinance or resolution delegates authority to approve, conditionally approve, or disapprove municipal stormwater management plans and implementing ordinances.

"Department" means the Department of Environmental Protection.

"Designated Center" means a State Development and Redevelopment Plan Center as designated by the State Planning Commission such as urban, regional, town, village, or hamlet.

"Design engineer" means a person professionally qualified and duly licensed in New Jersey to perform engineering services that may include, but not necessarily be limited to, development of project requirements, creation and development of project design and preparation of drawings and specifications.

"Development" means the division of a parcel of land into two or more parcels, the construction, reconstruction, conversion, structural alteration, relocation or enlarge-enlargement of any building or structure, any mining excavation or landfill, and any use or change in the use of any building or other structure, or land or extension of use of land, for which permission is required under the Municipal Land Use Law, N.J.S.A. 40:55D-1 *et seq*.

> In the case of development of agricultural land, development means: any activity that requires a State permit, any activity reviewed by the County Agricultural Board (CAB) and the State Agricultural Development Committee (SADC), and municipal review of any activity not exempted by the Right to Farm Act , N.J.S.A 4:1C-1 et seq.

"Disturbance" means the placement or reconstruction of impervious surface or motor vehicle surface, or exposure and/or movement of soil or bedrock or clearing, cutting, or removing of vegetation. Milling and repaving is not considered disturbance for the purposes of this definition.

"Drainage area" means a geographic area within which stormwater, sediments, or dissolved materials drain to a particular receiving waterbody or to a particular point along a receiving waterbody.

"Environmentally constrained area" means the following areas where the physical alteration of the land is in some way restricted, either through regulation, easement, deed restriction or ownership such as: wetlands, floodplains, threatened and endangered species sites or designated habitats, and parks and preserves. Habitats of endangered or threatened species are identified using the Department's Landscape Project as approved by the Department's Endangered and Nongame Species Program.

"Environmentally critical area" means an area or feature which is of significant environmental value, including but not limited to: stream corridors, natural heritage priority sites, habitats of endangered or threatened species, large areas of contiguous open space or upland forest, steep slopes, and well head protection and groundwater recharge areas. Habitats of endangered or threatened species are identified using the Department's Landscape Project as approved by the Department's Endangered and Nongame Species Program.

"Empowerment Neighborhoods" means neighborhoods designated by the Urban Coordinating Council "in consultation and conjunction with" the New Jersey Redevelopment Authority pursuant to N.J.S.A 55:19-69.

"Erosion" means the detachment and movement of soil or rock fragments by water, wind, ice, or gravity.

"Green infrastructure" means a stormwater management measure that manages stormwater close to its source by:

1. Treating stormwater runoff through infiltration into subsoil;
2. Treating stormwater runoff through filtration by vegetation or soil; or
3. Storing stormwater runoff for reuse.

"HUC 14" or "hydrologic unit code 14" means an area within which water drains to a particular receiving surface water body, also known as a subwatershed, which is identified by a 14-digit hydrologic unit boundary designation, delineated within New Jersey by the United States Geological Survey.

"Impervious surface" means a surface that has been covered with a layer of material so that it is highly resistant to infiltration by water.

"Infiltration" is the process by which water seeps into the soil from precipitation.

"Lead planning agency" means one or more public entities having stormwater management planning authority designated by the regional stormwater management planning committee pursuant to N.J.A.C. 7:8-3.2, that serves as the primary representative of the committee.

"Major development" means an individual "development," as well as multiple developments that individually or collectively result in:

1. The disturbance of one or more acres of land since February 2, 2004;
2. The creation of one-quarter acre or more of "regulated impervious surface" since February 2, 2004;
   The creation of one-quarter acre or more of "regulated motor vehicle surface" since March 2, 2021; or
3. A combination of 2 and 3 above that totals an area of one-quarter acre or more. The same surface shall not be counted twice when determining if the combination area equals one-quarter acre or more.

Major development includes all developments that are part of a common plan of development or sale (for example, phased residential development) that collectively or individually meet any one or more of paragraphs 1, 2, 3, or 4 above. Projects undertaken by any government agency that otherwise meet the definition of "major development" but which do not require approval

under the Municipal Land Use Law, N.J.S.A. 40:55D-1 et seq., are also considered "major development."

"Motor vehicle" means land vehicles propelled other than by muscular power, such as automobiles, motorcycles, autocycles, and low speed vehicles. For the purposes of this definition, motor vehicle does not include farm equipment, snowmobiles, all-terrain vehicles, motorized wheelchairs, go-carts, gas buggies, golf carts, ski-slope grooming machines, or vehicles that run only on rails or tracks.

"Motor vehicle surface" means any pervious or impervious surface that is intended to be used by "motor vehicles" and/or aircraft, and is directly exposed to precipitation including, but not limited to, driveways, parking areas, parking garages, roads, racetracks, and runways.

"Municipality" means any city, borough, town, township, or village.

"New Jersey Stormwater Best Management Practices (BMP) Manual" or "BMP Manual" means the manual maintained by the Department providing, in part, design specifications, removal rates, calculation methods, and soil testing procedures approved by the Department as being capable of contributing to the achievement of the stormwater management standards specified in this Chapter. The BMP Manual is periodically amended by the Department as necessary to provide design specifications on additional best management practices and new information on already included practices reflecting the best available current information regarding the particular practice and the Department's determination as to the ability of that best management practice to contribute to compliance with the standards contained in this Chapter. Alternative stormwater management measures, removal rates, or calculation methods may be utilized, subject to any limitations specified in this Chapter, provided the design engineer demonstrates to the municipality, in accordance with Section IV.F. of this ordinance and N.J.A.C. 7:8-5.2(g), that the proposed measure and its design will contribute to achievement of the design and performance standards established by this Chapter.

"Node" means an area designated by the State Planning Commission concentrating facilities and activities which are not organized in a compact form.

"Nutrient" means a chemical element or compound, such as nitrogen or phosphorus, which is essential to and promotes the development of organisms.

"Person" means any individual, corporation, company, partnership, firm, association, political subdivision of this State and any state, interstate or Federal agency.

"Pollutant" means any dredged spoil, solid waste, incinerator residue, filter backwash, sewage, garbage, refuse, oil, grease, sewage sludge, munitions, chemical wastes, biological materials, medical wastes, radioactive substance

(except those regulated under the Atomic Energy Act of 1954, as amended (42 U.S.C. §§ 2011 *et seq.*)), thermal waste, wrecked or discarded equipment, rock, sand, cellar dirt, industrial, municipal, agricultural, and construction waste or runoff, or other residue discharged directly or indirectly to the land, ground waters or surface waters of the State, or to a domestic treatment works. "Pollutant" includes both hazardous and nonhazardous pollutants.

"Recharge" means the amount of water from precipitation that infiltrates into the ground and is not evapotranspired.

"Regulated impervious surface" means any of the following, alone or in combination:

1. A net increase of impervious surface;
2. The total area of impervious surface collected by a new stormwater conveyance system (for the purpose of this definition, a "new stormwater conveyance system" is a stormwater conveyance system that is constructed where one did not exist immediately prior to its construction, or an existing system for which a new discharge location is created);
3. The total area of impervious surface proposed to be newly collected by an existing stormwater conveyance system; and/or
4. The total area of impervious surface collected by an existing stormwater conveyance system where the capacity of that conveyance system is increased.

"Regulated motor vehicle surface" means any of the following, alone or in combination:

1. The total area of motor vehicle surface that is currently receiving water;
2. A net increase in motor vehicle surface; and/or quality treatment either by vegetation or soil, by an existing stormwater management measure, or by treatment at a wastewater treatment plant, where the water quality treatment will be modified or removed.

"Sediment" means solid material, mineral or organic, that is in suspension, is being transported, or has been moved from its site of origin by air, water or gravity as a product of erosion.

"Site" means the lot or lots upon which a major development is to occur or has occurred.

"Soil" means all unconsolidated mineral and organic material of any origin.

"State Development and Redevelopment Plan Metropolitan Planning Area (PA1)" means an area delineated on the State Plan Policy Map and adopted by the State Planning Commission that is intended to be the focus for much of the State's future redevelopment and revitalization efforts.

"State Plan Policy Map" is defined as the geographic application of the State Development and Redevelopment Plan's goals and statewide policies, and the official map of these goals and policies.

"Stormwater" means water resulting from precipitation (including rain and snow) that runs off the land's surface, is transmitted to the subsurface, or is captured by separate storm sewers or other sewage or drainage facilities, or conveyed by snow removal equipment.

"Stormwater management BMP" means an excavation or embankment and related areas designed to retain stormwater runoff. A stormwater management BMP may either be normally dry (that is, a detention basin or infiltration system), retain water in a permanent pool (a retention basin), or be planted mainly with wetland vegetation (most constructed stormwater wetlands).

"Stormwater management measure" means any practice, technology, process, program, or other method intended to control or reduce stormwater runoff and associated pollutants, or to induce or control the infiltration or groundwater recharge of stormwater or to eliminate illicit or illegal non-stormwater discharges into stormwater conveyances.

"Stormwater runoff" means water flow on the surface of the ground or in storm sewers, resulting from precipitation.

"Stormwater management planning agency" means a public body authorized by legislation to prepare stormwater management plans.

"Stormwater management planning area" means the geographic area for which a stormwater management planning agency is authorized to prepare stormwater management plans, or a specific portion of that area identified in a stormwater management plan prepared by that agency.

"Tidal Flood Hazard Area" means a flood hazard area in which the flood elevation resulting from the two-, 10-, or 100-year storm, as applicable, is governed by tidal flooding from the Atlantic Ocean. Flooding in a tidal flood hazard area may be contributed to, or influenced by, stormwater runoff from inland areas, but the depth of flooding generated by the tidal rise and fall of the Atlantic Ocean is greater than flooding from any fluvial sources. In some situations, depending upon the extent of the storm surge from a particular storm event, a flood hazard area may be tidal in the 100-year storm, but fluvial in more frequent storm events.

"Urban Coordinating Council Empowerment Neighborhood" means a neighborhood given priority access to State resources through the New Jersey Redevelopment Authority.

"Urban Enterprise Zones" means a zone designated by the New Jersey Enterprise Zone Authority pursuant to the New Jersey Urban Enterprise Zones Act, N.J.S.A. 52:27H-60 et. seq.

"Urban Redevelopment Area" is defined as previously developed portions of areas:

1. Delineated on the State Plan Policy Map (SPPM) as the Metropolitan Planning Area (PA1), Designated Centers, Cores or Nodes;
2. Designated as CAFRA Centers, Cores or Nodes;
3. Designated as Urban Enterprise Zones; and
4. Designated as Urban Coordinating Council Empowerment Neighborhoods.

"Water control structure" means a structure within, or adjacent to water, which intentionally or coincidentally alters the hydraulic capacity, the flood elevation resulting from the two-, 10-, or 100-year storm, flood hazard area limit, and/or floodway limit of the water. Examples of a water control structure may include a bridge, culvert, dam, embankment, ford (if above grade), retaining wall, and weir.

"Waters of the State" means the ocean and its estuaries, all springs, streams, wetlands, and bodies of surface or groundwater, whether natural or artificial, within the boundaries of the State of New Jersey or subject to its jurisdiction.

"Wetlands" or "wetland" means an area that is inundated or saturated by surface water or ground water at a frequency and duration sufficient to support, and that under normal circumstances does support, a prevalence of vegetation typically adapted for life in saturated soil conditions, commonly known as hydrophytic vegetation.

SECTION III: DESIGN AND PERFORMANCE STANDARDS FOR STORMWATER MANAGEMENT MEASURES.

A. Stormwater management measures for major development shall be designed to provide erosion control, groundwater recharge, stormwater runoff quantity control, and stormwater runoff quality treatment as follows:

   1. The minimum standards for erosion control are those established under the Soil and Sediment Control Act, N.J.S.A. 4:24-39 et seq., and implementing rules at N.J.A.C. 2:90.
   2. The minimum standards for groundwater recharge, stormwater quality, and stormwater runoff quantity shall be met by incorporating green infrastructure.

B. The standards in this ordinance apply only to new major development and are intended to minimize the impact of stormwater runoff on water quality and water quantity in receiving water bodies and maintain groundwater recharge. The standards do not apply to new major development to the extent that alternative

design and performance standards are applicable under a regional stormwater management plan or Water Quality Management Plan adopted in accordance with Department rules.

SECTION IV: STORMWATER MANAGEMENT REQUIREMENTS FOR MAJOR DEVELOPMENT.

A. The development shall incorporate a maintenance plan for the stormwater management measures incorporated into the design of a major development in accordance with Section X.

B. Stormwater management measures shall avoid adverse impacts of concentrated flow on habitats for threatened and endangered species as documented in the Department's Landscape Project or Natural Heritage Database established under N.J.S.A. 13:1B-15.147 through 15.150, particularly *Helonias bullata* (swamp pink) and/or *Clemmys muhlnebergi* (bog turtle).

C. The following linear development projects are exempt from the groundwater recharge, stormwater runoff quality, and stormwater runoff quantity requirements of Section IV.P, Q and R:

1. The construction of an underground utility line provided that the disturbed areas are revegetated upon completion;
2. The construction of an aboveground utility line provided that the existing conditions are maintained to the maximum extent practicable; and
3. The construction of a public pedestrian access, such as a sidewalk or trail with a maximum width of 14 feet, provided that the access is made of permeable material.

D. A waiver from strict compliance from the green infrastructure, groundwater recharge, stormwater runoff quality, and stormwater runoff quantity requirements of Section IV.O, P, Q and R may be obtained for the enlargement of an existing public roadway or railroad; or the construction or enlargement of a public pedestrian access, provided that the following conditions are met:

1. The applicant demonstrates that there is a public need for the project that cannot be accomplished by any other means;
2. The applicant demonstrates through an alternatives analysis, that through the use of stormwater management measures, the option selected complies with the requirements of Section IV.O, P, Q and R to the maximum extent practicable;
3. The applicant demonstrates that, in order to meet the requirements of Section IV.O, P, Q and R, existing structures currently in use, such as homes and buildings, would need to be condemned; and
4. The applicant demonstrates that it does not own or have other rights to areas, including the potential to obtain through condemnation lands not falling under IV.D.3 above within the upstream drainage area of the receiving stream, that

would provide additional opportunities to mitigate the requirements of Section IV.O, P, Q and R that were not achievable onsite.

E. Tables 1 through 3 below summarize the ability of stormwater best management practices identified and described in the New Jersey Stormwater Best Management Practices Manual to satisfy the green infrastructure, groundwater recharge, stormwater runoff quality and stormwater runoff quantity standards specified in Section IV.O, P, Q and R. When designed in accordance with the most current version of the New Jersey Stormwater Best Management Practices Manual, the stormwater management measures found at N.J.A.C. 7:8-5.2 (f) Tables 5-1, 5-2 and 5-3 and listed below in Tables 1, 2 and 3 are presumed to be capable of providing stormwater controls for the design and performance standards as outlined in the tables below. Upon amendments of the New Jersey Stormwater Best Management Practices to reflect additions or deletions of BMPs meeting these standards, or changes in the presumed performance of BMPs designed in accordance with the New Jersey Stormwater BMP Manual, the Department shall publish in the New Jersey Registers a notice of administrative change revising the applicable table. The most current version of the BMP Manual can be found on the Department's website at:

https://njstormwater.org/bmp_manual2.htm.

F. Where the BMP tables in the NJ Stormwater Management Rule are different due to updates or amendments with the tables in this ordinance the BMP Tables in the Stormwater Management rule at N.J.A.C. 7:8-5.2(f) shall take precedence.

ORD 1565

Table 1 Green Infrastructure BMPs for Groundwater Recharge, Stormwater Runoff Quality, and/or Stormwater Runoff Quantity				
Best Management Practice	**Stormwater Runoff Quality TSS Removal Rate (percent)**	**Stormwater Runoff Quantity**	**Groundwater Recharge**	**Minimum Separation from Seasonal High Water Table (feet)**
Cistern	0	Yes	No	--
Dry Well[a]	0	No	Yes	2
Grass Swale	50 or less	No	No	2[e] 1[f]
Green Roof	0	Yes	No	--
Manufactured Treatment Device[a] [g]	50 or 80	No	No	Dependent upon the device
Pervious Paving System[a]	80	Yes	Yes[b] No[c]	2[b] 1[c]
Small-Scale Bioretention Basin[a]	80 or 90	Yes	Yes[b] No[c]	2[b] 1[c]
Small-Scale Infiltration Basin[a]	80	Yes	Yes	2
Small-Scale Sand Filter	80	Yes	Yes	2
Vegetative Filter Strip	60-80	No	No	--

(Notes corresponding to annotations (a) *through* (g) *are found on Page 14)*

ORD 1565

Table 2 Green Infrastructure BMPs for Stormwater Runoff Quantity (or for Groundwater Recharge and/or Stormwater Runoff Quality with a Waiver or Variance from N.J.A.C. 7:8-5.3)				
Best Management Practice	**Stormwater Runoff Quality TSS Removal Rate (percent)**	**Stormwater Runoff Quantity**	**Groundwater Recharge**	**Minimum Separation from Seasonal High Water Table (feet)**
Bioretention System	80 or 90	Yes	Yes[b] No[c]	2[b] 1[c]
Infiltration Basin	80	Yes	Yes	2
Sand Filter[b]	80	Yes	Yes	2
Standard Constructed Wetland	90	Yes	No	N/A
Wet Pond[d]	50-90	Yes	No	N/A

(Notes corresponding to annotations (b) *through* (d) *are found on Page 14)*

ORD 1565

Table 3 BMPs for Groundwater Recharge, Stormwater Runoff Quality, and/or Stormwater Runoff Quantity only with a Waiver or Variance from N.J.A.C. 7:8-5.3				
Best Management Practice	**Stormwater Runoff Quality TSS Removal Rate (percent)**	**Stormwater Runoff Quantity**	**Groundwater Recharge**	**Minimum Separation from Seasonal High Water Table (feet)**
Blue Roof	0	Yes	No	N/A
Extended Detention Basin	40-60	Yes	No	1
Manufactured Treatment Device[(h)]	50 or 80	No	No	Dependent upon the device
Sand Filter[(c)]	80	Yes	No	1
Subsurface Gravel Wetland	90	No	No	1
Wet Pond	50-90	Yes	No	N/A

Notes to Tables 1, 2, and 3:

(a) subject to the applicable contributory drainage area limitation specified at Section IV.O.2;
(b) designed to infiltrate into the subsoil;
(c) designed with underdrains;
(d) designed to maintain at least a 10-foot wide area of native vegetation along at least fifty (50%) percent of the shoreline and to include a stormwater runoff retention component designed to capture stormwater runoff for beneficial reuse, such as irrigation;
(e) designed with a slope of less than two (2%) percent;
(f) designed with a slope of equal to or greater than two (2%) percent;
(g) manufactured treatment devices that meet the definition of green infrastructure at Section II;
(h) manufactured treatment devices that do not meet the definition of green infrastructure at Section II.

G. An alternative stormwater management measure, alternative removal rate, and/or alternative method to calculate the removal rate may be used if the design engineer demonstrates the capability of the proposed alternative stormwater management measure and/or the validity of the alternative rate or method to the municipality. A copy of any approved alternative stormwater management measure, alternative removal rate, and/or alternative method to calculate the removal rate shall be provided to the Department in accordance with Section VI.B. Alternative stormwater management measures may be used to satisfy the requirements at Section IV.O only if the measures meet the definition of "green infrastructure" in Section II. Alternative stormwater management measures that function in a similar manner to a BMP listed at Section O.2 are subject to the contributory drainage area limitation specified at Section O.2 for that similarly functioning BMP. Alternative stormwater management measures approved in accordance with this subsection that do not function in a similar manner to any BMP listed at Section O.2 shall have a contributory drainage area less than or equal to 2.5 acres, except for alternative stormwater management measures that function similarly to cisterns, grass swales, green roofs, standard constructed wetlands, vegetative filter strips, and wet ponds, which are not subject to a contributory drainage area limitation. Alternative measures that function similarly to standard constructed wetlands or wet ponds shall not be used for compliance with the stormwater runoff quality standard unless a variance in accordance with N.J.A.C. 7:8-4.6 or a waiver from strict compliance in accordance with Section IV.D is granted from Section IV.O.

H. Whenever the stormwater management design includes one or more BMPs that will infiltrate stormwater into subsoil, the design engineer shall assess the hydraulic impact on the groundwater table and design the site, so as to avoid adverse hydraulic impacts. Potential adverse hydraulic impacts include, but are not limited to, exacerbating a naturally or seasonally high water table, so as to cause surficial ponding, flooding of basements, or interference with the proper operation of subsurface sewage disposal systems or other subsurface structures within the zone of influence of the groundwater mound, or interference with the proper functioning of the stormwater management measure itself.

I. Design standards for stormwater management measures are as follows:

1. Stormwater management measures shall be designed to take into account the existing site conditions, including, but not limited to, environmentally critical areas; wetlands; flood-prone areas; slopes; depth to seasonal high water table; soil type, permeability, and texture; drainage area and drainage patterns; and the presence of solution-prone carbonate rocks (limestone);
2. Stormwater management measures shall be designed to minimize maintenance, facilitate maintenance and repairs, and ensure proper functioning. Trash racks shall be installed at the intake to the outlet structure, as appropriate, and shall have parallel bars with one-inch spacing between the bars to the elevation of the water quality design storm. For elevations higher than the water quality design storm, the parallel bars at the outlet structure

shall be spaced no greater than one-third the width of the diameter of the orifice or one-third the width of the weir, with a minimum spacing between bars of one inch and a maximum spacing between bars of six inches. In addition, the design of trash racks must comply with the requirements of Section VIII.C;

3. Stormwater management measures shall be designed, constructed, and installed to be strong, durable, and corrosion resistant. Measures that are consistent with the relevant portions of the Residential Site Improvement Standards at N.J.A.C. 5:21-7.3, 7.4, and 7.5 shall be deemed to meet this requirement;
4. Stormwater management BMPs shall be designed to meet the minimum safety standards for stormwater management BMPs at Section VIII; and
5. The size of the orifice at the intake to the outlet from the stormwater management BMP shall be a minimum of two and one-half inches in diameter.

J. Manufactured treatment devices may be used to meet the requirements of this subchapter, provided the pollutant removal rates are verified by the New Jersey Corporation for Advanced Technology and certified by the Department. Manufactured treatment devices that do not meet the definition of green infrastructure at Section II may be used only under the circumstances described at Section IV.O.4.

K. Any application for a new agricultural development that meets the definition of major development at Section II shall be submitted to the Soil Conservation District for review and approval in accordance with the requirements at Sections IV.O, P, Q and R and any applicable Soil Conservation District guidelines for stormwater runoff quantity and erosion control. For purposes of this subsection, "agricultural development" means land uses normally associated with the production of food, fiber, and livestock for sale. Such uses do not include the development of land for the processing or sale of food and the manufacture of agriculturally related products.

L. If there is more than one drainage area, the groundwater recharge, stormwater runoff quality, and stormwater runoff quantity standards at Section IV.P, Q and R shall be met in each drainage area, unless the runoff from the drainage areas converge onsite and no adverse environmental impact would occur as a result of compliance with any one or more of the individual standards being determined utilizing a weighted average of the results achieved for that individual standard across the affected drainage areas.

M. Any stormwater management measure authorized under the municipal stormwater management plan or ordinance shall be reflected in a deed notice recorded in the Office of the County Clerk. A form of deed notice shall be submitted to the municipality for approval prior to filing. The deed notice shall contain a description of the stormwater management measure(s) used to meet the green infrastructure, groundwater recharge, stormwater runoff quality, and stormwater runoff quantity standards at Section IV.O, P, Q and R and shall identify the location of the stormwater management measure(s) in NAD 1983 State Plane New Jersey FIPS 2900 US Feet or Latitude and Longitude in decimal degrees. The deed notice shall also reference the maintenance plan required to be recorded upon the deed pursuant to Section X.B.5. Prior to the commencement of construction, proof that the above required deed notice has been filed shall be submitted to the municipality. Proof that the required information has been recorded on the deed shall be in the form of either a copy of the complete recorded document or a receipt from the clerk or other proof of recordation provided by the recording office. However, if the initial proof provided to the municipality is not a copy of the complete recorded document, a copy of the complete recorded document shall be provided to the municipality within 180 calendar days of the authorization granted by the municipality.

N. A stormwater management measure approved under the municipal stormwater management plan or ordinance may be altered or replaced with the approval of the municipality, if the municipality determines that the proposed alteration or replacement meets the design and performance standards pursuant to Section IV of this ordinance and provides the same level of stormwater management as the previously approved stormwater management measure that is being altered or replaced. If an alteration or replacement is approved, a revised deed notice shall be submitted to the municipality for approval and subsequently recorded with the Office of the County Clerk, and shall contain a description and location of the stormwater management measure, as well as reference to the maintenance plan, in accordance with "K" above. Prior to the commencement of construction, proof that the above required deed notice has been filed shall be submitted to the municipality in accordance with "K" above.

O. Green Infrastructure Standards

1. This subsection specifies the types of green infrastructure BMPs that may be used to satisfy the groundwater recharge, stormwater runoff quality, and stormwater runoff quantity standards.

2. To satisfy the groundwater recharge and stormwater runoff quality standards at Section IV.P and Q, the design engineer shall utilize green infrastructure BMPs identified in Table 1 at Section IV.F. and/or an alternative stormwater management measure approved in accordance with Section IV.G. The following green infrastructure BMPs are subject to the following maximum contributory drainage area limitations:

ORD 1565

Best Management Practice	Maximum Contributory Drainage Area
Dry Well	1 acre
Manufactured Treatment Device	2.5 acres
Pervious Pavement Systems	Area of additional inflow cannot exceed three times the area occupied by the BMP
Small-scale Bioretention Systems	2.5 acres
Small-scale Infiltration Basin	2.5 acres
Small-scale Sand Filter	2.5 acres

3. To satisfy the stormwater runoff quantity standards at Section IV.R, the design engineer shall utilize BMPs from Table 1 or from Table 2 and/or an alternative stormwater management measure approved in accordance with Section IV.G.

4. If a variance in accordance with N.J.A.C. 7:8-4.6 or a waiver from strict compliance in accordance with Section IV.D is granted from the requirements of this subsection, then BMPs from Table 1, 2, or 3, and/or an alternative stormwater management measure approved in accordance with Section IV.G may be used to meet the groundwater recharge, stormwater runoff quality, and stormwater runoff quantity standards at Section IV.P, Q and R.

5. For separate or combined storm sewer improvement projects, such as sewer separation, undertaken by a government agency or public utility (for example, a sewerage company), the requirements of this subsection shall only apply to areas owned in fee simple by the government agency or utility, and areas within a right-of-way or easement held or controlled by the government agency or utility; the entity shall not be required to obtain additional property or property rights to fully satisfy the requirements of this subsection. Regardless of the amount of area of a separate or combined storm sewer improvement project subject to the green infrastructure requirements of this subsection, each project shall fully comply with the applicable groundwater recharge, stormwater runoff quality control, and stormwater runoff quantity standards at Section IV.P, Q and R, unless the project is granted a waiver from strict compliance in accordance with Section IV.D.

P. Groundwater Recharge Standards

1. This subsection contains the minimum design and performance standards for groundwater recharge as follows:
2. The design engineer shall, using the assumptions and factors for stormwater runoff and groundwater recharge calculations at Section V, either:
   i. Demonstrate through hydrologic and hydraulic analysis that the site and its stormwater management measures maintain one-hundred (100%) percent of the average annual pre-construction groundwater recharge volume for the site; or
   ii. Demonstrate through hydrologic and hydraulic analysis that the increase of stormwater runoff volume from pre-construction to post-construction for the 2-year storm is infiltrated.

3. This groundwater recharge requirement does not apply to projects within the "urban redevelopment area," or to projects subject to 4 below.

4. The following types of stormwater shall not be recharged:

   i. Stormwater from areas of high pollutant loading. High pollutant loading areas are areas in industrial and commercial developments where solvents and/or petroleum products are loaded/unloaded, stored, or applied, areas where pesticides are loaded/unloaded or stored; areas where hazardous materials are expected to be present in greater than "reportable quantities" as defined by the United States Environmental Protection Agency (EPA) at 40 CFR 302.4; areas where recharge would be inconsistent with Department approved remedial action work plan or landfill closure plan and areas with high risks for spills of toxic materials, such as gas stations and vehicle maintenance facilities; and
   ii. Industrial stormwater exposed to "source material." "Source material" means any material(s) or machinery, located at an industrial facility that is directly or indirectly related to process, manufacturing or other industrial activities, which could be a source of pollutants in any industrial stormwater discharge to groundwater. Source materials include, but are not limited to, raw materials; intermediate products; final products; waste materials; by-products; industrial machinery and fuels, and lubricants, solvents, and detergents that are related to process, manufacturing, or other industrial activities that are exposed to stormwater.

Q. Stormwater Runoff Quality Standards

1. This subsection contains the minimum design and performance standards to control stormwater runoff quality impacts of major developments. Stormwater runoff quality standards are applicable when the major development results in an increase of one-quarter acre or more of regulated motor vehicle surface.
2. Stormwater management measures shall be designed to reduce the post-construction load of total suspended solids (TSS) in stormwater runoff generated from the water quality design storm as follows:

ORD 1565

i. Eighty (80%) percent TSS removal of the anticipated load, expressed as an annual average shall be achieved for the stormwater runoff from the net increase of motor vehicle surface.
ii. If the surface is considered a regulated motor vehicle surface because the water quality treatment for an area of motor vehicle surface that is currently receiving water quality treatment either by vegetation or soil, by an existing stormwater management measure, or by treatment at a wastewater treatment plant is to be modified or removed, the project shall maintain or increase the existing TSS removal of the anticipated load expressed as an annual average.

3. The requirement to reduce TSS does not apply to any stormwater runoff in a discharge regulated under a numeric effluent limitation for TSS imposed under the New Jersey Pollutant Discharge Elimination System (NJPDES) rules, N.J.A.C. 7:14A, or in a discharge specifically exempt under a NJPDES permit from this requirement. Every major development, including any that discharge into a combined sewer system, shall comply with 2 above, unless the major development is itself subject to a NJPDES permit with a numeric effluent limitation for TSS or the NJPDES permit to which the major development is subject exempts the development from a numeric effluent limitation for TSS.
4. The water quality design storm is 1.25 inches of rainfall in two hours. Water quality calculations shall take into account the distribution of rain from the water quality design storm, as reflected in Table 4, below. The calculation of the volume of runoff may take into account the implementation of stormwater management measures.

ORD 1565

Table 4 - Water Quality Design Storm Distribution

Time (Minutes)	Cumulative Rainfall (Inches)	Time (Minutes)	Cumulative Rainfall (Inches)	Time (Minutes)	Cumulative Rainfall (Inches)
1	0.00166	41	0.1728	81	1.0906
2	0.00332	42	0.1796	82	1.0972
3	0.00498	43	0.1864	83	1.1038
4	0.00664	44	0.1932	84	1.1104
5	0.00830	45	0.2000	85	1.1170
6	0.00996	46	0.2117	86	1.1236
7	0.01162	47	0.2233	87	1.1302
8	0.01328	48	0.2350	88	1.1368
9	0.01494	49	0.2466	89	1.1434
10	0.01660	50	0.2583	90	1.1500
11	0.01828	51	0.2783	91	1.1550
12	0.01996	52	0.2983	92	1.1600
13	0.02164	53	0.3183	93	1.1650
14	0.02332	54	0.3383	94	1.1700
15	0.02500	55	0.3583	95	1.1750
16	0.03000	56	0.4116	96	1.1800
17	0.03500	57	0.4650	97	1.1850
18	0.04000	58	0.5183	98	1.1900
19	0.04500	59	0.5717	99	1.1950
20	0.05000	60	0.6250	100	1.2000
21	0.05500	61	0.6783	101	1.2050
22	0.06000	62	0.7317	102	1.2100
23	0.06500	63	0.7850	103	1.2150
24	0.07000	64	0.8384	104	1.2200
25	0.07500	65	0.8917	105	1.2250
26	0.08000	66	0.9117	106	1.2267
27	0.08500	67	0.9317	107	1.2284
28	0.09000	68	0.9517	108	1.2300
29	0.09500	69	0.9717	109	1.2317
30	0.10000	70	0.9917	110	1.2334
31	0.10660	71	1.0034	111	1.2351
32	0.11320	72	1.0150	112	1.2367
33	0.11980	73	1.0267	113	1.2384
34	0.12640	74	1.0383	114	1.2400
35	0.13300	75	1.0500	115	1.2417
36	0.13960	76	1.0568	116	1.2434
37	0.14620	77	1.0636	117	1.2450
38	0.15280	78	1.0704	118	1.2467
39	0.15940	79	1.0772	119	1.2483
40	0.16600	80	1.0840	120	1.2500

5. If more than one BMP in series is necessary to achieve the required eighty (80%) percent TSS reduction for a site, the applicant shall utilize the following formula to calculate TSS reduction:

ORD 1565

$R = A + B - (A \times B) / 100$,
Where

R = total TSS Percent Load Removal from application of both BMPs, and
A = the TSS Percent Removal Rate applicable to the first BMP
B = the TSS Percent Removal Rate applicable to the second BMP.

6. Stormwater management measures shall also be designed to reduce, to the maximum extent feasible, the post-construction nutrient load of the anticipated load from the developed site in stormwater runoff generated from the water quality design storm. In achieving reduction of nutrients to the maximum extent feasible, the design of the site shall include green infrastructure BMPs that optimize nutrient removal while still achieving the performance standards in Section IV.P, Q and R.
7. In accordance with the definition of FW1 at N.J.A.C. 7:9B-1.4, stormwater management measures shall be designed to prevent any increase in stormwater runoff to waters classified as FW1.
8. The Flood Hazard Area Control Act Rules at N.J.A.C. 7:13-4.1(c)1 establishes 300-foot riparian zones along Category One waters, as designated in the Surface Water Quality Standards at N.J.A.C. 7:9B, and certain upstream tributaries to Category One waters. A person shall not undertake a major development that is located within or discharges into a 300-foot riparian zone without prior authorization from the Department under N.J.A.C. 7:13.
9. Pursuant to the Flood Hazard Area Control Act Rules at N.J.A.C. 7:13-11.2(j)3.i, runoff from the water quality design storm that is discharged within a 300-foot riparian zone shall be treated in accordance with this subsection to reduce the post-construction load of total suspended solids by ninety-five (95%) percent of the anticipated load from the developed site, expressed as an annual average.
10. This stormwater runoff quality standards do not apply to the construction of one individual single-family dwelling, provided that it is not part of a larger development or subdivision that has received preliminary or final site plan approval prior to December 3, 2018, and that the motor vehicle surfaces are made of permeable material(s) such as gravel, dirt, and/or shells.

R. Stormwater Runoff Quantity Standards

1. This subsection contains the minimum design and performance standards to control stormwater runoff quantity impacts of major development.
2. In order to control stormwater runoff quantity impacts, the design engineer shall, using the assumptions and factors for stormwater runoff calculations at Section V, complete one of the following:

   i. Demonstrate through hydrologic and hydraulic analysis that for stormwater leaving the site, post-construction runoff hydrographs for the

2-, 10-, and 100-year storm events do not exceed, at any point in time, the pre-construction runoff hydrographs for the same storm events;

ii. Demonstrate through hydrologic and hydraulic analysis that there is no increase, as compared to the pre-construction condition, in the peak runoff rates of stormwater leaving the site for the 2-, 10- and 100-year storm events and that the increased volume or change in timing of stormwater runoff will not increase flood damage at or downstream of the site. This analysis shall include the analysis of impacts of existing land uses and projected land uses assuming full development under existing zoning and land use ordinances in the drainage area;

iii. Design stormwater management measures so that the post-construction peak runoff rates for the 2-, 10- and 100-year storm events are 50, 75 and 80 percent, respectively, of the pre-construction peak runoff rates. The percentages apply only to the post-construction stormwater runoff that is attributable to the portion of the site on which the proposed development or project is to be constructed; or

iv. In tidal flood hazard areas, stormwater runoff quantity analysis in accordance with 2.i, ii and iii above is required unless the design engineer demonstrates through hydrologic and hydraulic analysis that the increased volume, change in timing, or increased rate of the stormwater runoff, or any combination of the three will not result in additional flood damage below the point of discharge of the major development. No analysis is required if the stormwater is discharged directly into any ocean, bay, inlet, or the reach of any watercourse between its confluence with an ocean, bay, or inlet and downstream of the first water control structure.

3. The stormwater runoff quantity standards shall be applied at the site's boundary to each abutting lot, roadway, watercourse, or receiving storm sewer system.

SECTION V: CALCULATION OF STORMWATER RUNOFF AND GROUNDWATER RECHARGE.

A. Stormwater runoff shall be calculated in accordance with the following:

1. The design engineer shall calculate runoff using one of the following methods:

i. The USDA Natural Resources Conservation Service (NRCS) methodology, including the NRCS Runoff Equation and Dimensionless Unit Hydrograph, as described in Chapters 7, 9, 10, 15 and 16 Part 630, Hydrology National Engineering Handbook, incorporated herein by reference as amended and supplemented. This methodology is additionally described in *Technical Release 55 - Urban Hydrology for Small Watersheds* (TR-55), dated June 1986, incorporated herein by reference as amended and supplemented. Information regarding the

methodology is available from the Natural Resources Conservation Service website at:

https://www.nrcs.usda.gov/Internet/FSE_DOCUMENTS/stelprdb1044171.pdf

or at United States Department of Agriculture Natural Resources Conservation Service, 220 Davison Avenue, Somerset, New Jersey 08873; or

ii. The Rational Method for peak flow and the Modified Rational Method for hydrograph computations. The rational and modified rational methods are described in "Appendix A-9 Modified Rational Method" in the Standards for Soil Erosion and Sediment Control in New Jersey, January 2014. This document is available from the State Soil Conservation Committee or any of the Soil Conservation Districts listed at N.J.A.C. 2:90-1.3(a)3. The location, address, and telephone number for each Soil Conservation District is available from the State Soil Conservation Committee, PO Box 330, Trenton, New Jersey 08625. The document is also available at:

http://www.nj.gov/agriculture/divisions/anr/pdf/2014NJSoilErosionControlStandardsComplete.pdf.

2. For the purpose of calculating runoff coefficients and groundwater recharge, there is a presumption that the pre-construction condition of a site or portion thereof is a wooded land use with good hydrologic condition. The term "runoff coefficient" applies to both the NRCS methodology above at Section V.A.1.i and the Rational and Modified Rational Methods at Section V.A.1.ii. A runoff coefficient or a groundwater recharge land cover for an existing condition may be used on all or a portion of the site if the design engineer verifies that the hydrologic condition has existed on the site or portion of the site for at least five years without interruption prior to the time of application. If more than one land cover have existed on the site during the five years immediately prior to the time of application, the land cover with the lowest runoff potential shall be used for the computations. In addition, there is the presumption that the site is in good hydrologic condition (if the land use type is pasture, lawn, or park), with good cover (if the land use type is woods), or with good hydrologic condition and conservation treatment (if the land use type is cultivation).

3. In computing pre-construction stormwater runoff, the design engineer shall account for all significant land features and structures, such as ponds, wetlands, depressions, hedgerows, or culverts, that may reduce pre-construction stormwater runoff rates and volumes.

4. In computing stormwater runoff from all design storms, the design engineer shall consider the relative stormwater runoff rates and/or volumes of pervious

and impervious surfaces separately to accurately compute the rates and volume of stormwater runoff from the site. To calculate runoff from unconnected impervious cover, urban impervious area modifications as described in the NRCS *Technical Release 55 – Urban Hydrology for Small Watersheds* or other methods may be employed.

5. If the invert of the outlet structure of a stormwater management measure is below the flood hazard design flood elevation as defined at N.J.A.C. 7:13, the design engineer shall take into account the effects of tailwater in the design of structural stormwater management measures.

B. Groundwater recharge may be calculated in accordance with the following:

The New Jersey Geological Survey Report GSR-32, A Method for Evaluating Groundwater-Recharge Areas in New Jersey, incorporated herein by reference as amended and supplemented. Information regarding the methodology is available from the New Jersey Stormwater Best Management Practices Manual; at the New Jersey Geological Survey website at:

https://www.nj.gov/dep/njgs/pricelst/gsreport/gsr32.pdf

or at New Jersey Geological and Water Survey, 29 Arctic Parkway, PO Box 420 Mail Code 29-01, Trenton, New Jersey 08625-0420.

SECTION VI: SOURCES FOR TECHNICAL GUIDANCE.

A. Technical guidance for stormwater management measures can be found in the documents listed below, which are available to download from the Department's website at:

http://www.nj.gov/dep/stormwater/bmp_manual2.htm.

1. Guidelines for stormwater management measures are contained in the New Jersey Stormwater Best Management Practices Manual, as amended and supplemented. Information is provided on stormwater management measures such as, but not limited to, those listed in Tables 1, 2, and 3.
2. Additional maintenance guidance is available on the Department's website at:

https://www.njstormwater.org/maintenance_guidance.htm.

B. Submissions required for review by the Department should be mailed to:

The Division of Water Quality, New Jersey Department of Environmental Protection, Mail Code 401-02B, PO Box 420, Trenton, New Jersey 08625-0420.

ORD 1565

SECTION VII: SOLIDS AND FLOATABLE MATERIALS CONTROL STANDARDS.

A. Site design features identified under Section IV.F above, or alternative designs in accordance with Section IV.G above, to prevent discharge of trash and debris from drainage systems shall comply with the following standard to control passage of solid and floatable materials through storm drain inlets. For purposes of this paragraph, "solid and floatable materials" means sediment, debris, trash, and other floating, suspended, or settleable solids. For exemptions to this standard see Section VII.A.2 below.

1. Design engineers shall use one of the following grates whenever they use a grate in pavement or another ground surface to collect stormwater from that surface into a storm drain or surface water body under that grate:

   i. The New Jersey Department of Transportation (NJDOT) bicycle safe grate, which is described in Chapter 2.4 of the NJDOT Bicycle Compatible Roadways and Bikeways Planning and Design Guidelines; or
   ii. A different grate, if each individual clear space in that grate has an area of no more than seven (7.0) square inches, or is no greater than 0.5 inches across the smallest dimension.

      Examples of grates subject to this standard include grates in grate inlets, the grate portion (non-curb-opening portion) of combination inlets, grates on storm sewer manholes, ditch grates, trench grates, and grates of spacer bars in slotted drains. Examples of ground surfaces include surfaces of roads (including bridges), driveways, parking areas, bikeways, plazas, sidewalks, lawns, fields, open channels, and stormwater system floors used to collect stormwater from the surface into a storm drain or surface water body.

   iii. For curb-opening inlets, including curb-opening inlets in combination inlets, the clear space in that curb opening, or each individual clear space if the curb opening has two or more clear spaces, shall have an area of no more than seven (7.0) square inches, or be no greater than two (2.0) inches across the smallest dimension.

2. The standard in A.1. above does not apply:

   i. Where each individual clear space in the curb opening in existing curb-opening inlet does not have an area of more than nine (9.0) square inches;
   ii. Where the municipality agrees that the standards would cause inadequate hydraulic performance that could not practicably be overcome by using additional or larger storm drain inlets;
   iii. Where flows from the water quality design storm as specified in N.J.A.C. 7:8 are conveyed through any device (e.g., end of pipe netting facility, manufactured treatment device, or a catch basin hood) that is designed, at

a minimum, to prevent delivery of all solid and floatable materials that could not pass through one of the following:

a. A rectangular space four and five-eighths (4.625) inches long and one and one-half (1.5) inches wide (this option does not apply for outfall netting facilities); or
b. A bar screen having a bar spacing of 0.5 inches.

Note that these exemptions do not authorize any infringement of requirements in the Residential Site Improvement Standards for bicycle safe grates in new residential development (N.J.A.C. 5:21-4.18(b)2 and 7.4(b)1).

iv. Where flows are conveyed through a trash rack that has parallel bars with one-inch (1 inch) spacing between the bars, to the elevation of the Water Quality Design Storm as specified in N.J.A.C. 7:8; or

v. Where the New Jersey Department of Environmental Protection determines, pursuant to the New Jersey Register of Historic Places Rules at N.J.A.C. 7:4-7.2(c), that action to meet this standard is an undertaking that constitutes an encroachment or will damage or destroy the New Jersey Register listed historic property.

SECTION VIII: SAFETY STANDARDS FOR STORMWATER MANAGEMENT BASINS.

A. This section sets forth requirements to protect public safety through the proper design and operation of stormwater management BMPs. This section applies to any new stormwater management BMP.

B. The provisions of this section are not intended to preempt more stringent municipal or county safety requirements for new or existing stormwater management BMPs. Municipal and county stormwater management plans and ordinances may, pursuant to their authority, require existing stormwater management BMPs to be retrofitted to meet one or more of the safety standards in Section VIII.C.1, VIII.C.2, and VIII.C.3 for trash racks, overflow grates, and escape provisions at outlet structures.

C. Requirements for Trash Racks, Overflow Grates and Escape Provisions

1. A trash rack is a device designed to catch trash and debris and prevent the clogging of outlet structures. Trash racks shall be installed at the intake to the outlet from the Stormwater management BMP to ensure proper functioning of the BMP outlets in accordance with the following:

i. The trash rack shall have parallel bars, with no greater than six-inch spacing between the bars;

ii. The trash rack shall be designed so as not to adversely affect the hydraulic performance of the outlet pipe or structure;
iii. The average velocity of flow through a clean trash rack is not to exceed 2.5 feet per second under the full range of stage and discharge. Velocity is to be computed on the basis of the net area of opening through the rack; and
iv. The trash rack shall be constructed of rigid, durable, and corrosion resistant material and designed to withstand a perpendicular live loading of 300 pounds per square foot.

2. An overflow grate is designed to prevent obstruction of the overflow structure. If an outlet structure has an overflow grate, such grate shall meet the following requirements:

   i. The overflow grate shall be secured to the outlet structure but removable for emergencies and maintenance.
   ii. The overflow grate spacing shall be no less than two inches across the smallest dimension
   iii. The overflow grate shall be constructed and installed to be rigid, durable, and corrosion resistant, and shall be designed to withstand a perpendicular live loading of 300 pounds per square foot.

3. Stormwater management BMPs shall include escape provisions as follows:

   i. If a stormwater management BMP has an outlet structure, escape provisions shall be incorporated in or on the structure. Escape provisions include the installation of permanent ladders, steps, rungs, or other features that provide easily accessible means of egress from stormwater management BMPs. With the prior approval of the municipality pursuant to VIII.C, a free-standing outlet structure may be exempted from this requirement;
   ii. Safety ledges shall be constructed on the slopes of all new stormwater management BMPs having a permanent pool of water deeper than two and one-half feet. Safety ledges shall be comprised of two steps. Each step shall be four to six feet in width. One step shall be located approximately two and one-half feet below the permanent water surface, and the second step shall be located one to one and one-half feet above the permanent water surface. See VIII.E for an illustration of safety ledges in a stormwater management BMP; and
   iii. In new stormwater management BMPs, the maximum interior slope for an earthen dam, embankment, or berm shall not be steeper than three horizontal to one vertical.

D. Variance or Exemption from Safety Standard

A variance or exemption from the safety standards for stormwater management BMPs may be granted only upon a written finding by the municipality that the variance or exemption will not constitute a threat to public safety.

ORD 1565

E. Safety Ledge Illustration

Elevation View –Basin Safety Ledge Configuration



SECTION IX: REQUIREMENTS FOR A SITE DEVELOPMENT STORMWATER PLAN.

A. Submission of Site Development Stormwater Plan

1. Whenever an applicant seeks municipal approval of a development subject to this ordinance, the applicant shall submit all of the required components of the Checklist for the Site Development Stormwater Plan at Section IX.C below as part of the submission of the application for approval.

2. The applicant shall demonstrate that the project meets the standards set forth in this ordinance.

3. The applicant shall submit two copies of the materials listed in the checklist for site development stormwater plans in accordance with Section IX.C of this ordinance.

B. Site Development Stormwater Plan Approval

The applicant's Site Development project shall be reviewed as a part of the review process by the municipal board or official from which municipal approval is sought. That municipal board or official shall consult the municipality's review engineer to determine if all of the checklist requirements have been satisfied and to determine if the project meets the standards set forth in this ordinance.

C. Submission of Site Development Stormwater Plan

ORD 1565

The following information shall be required:

1. Topographic Base Map

   The reviewing engineer may require upstream tributary drainage system information as necessary. It is recommended that the topographic base map of the site be submitted which extends a minimum of 200 feet beyond the limits of the proposed development, at a scale of 1"=200' or greater, showing 2-foot contour intervals. The map as appropriate may indicate the following: existing surface water drainage, shorelines, steep slopes, soils, erodible soils, perennial or intermittent streams that drain into or upstream of the Category One waters, wetlands and flood plains along with their appropriate buffer strips, marshlands and other wetlands, pervious or vegetative surfaces, existing man-made structures, roads, bearing and distances of property lines, and significant natural and manmade features not otherwise shown.

2. Environmental Site Analysis

   A written and graphic description of the natural and man-made features of the site and its surroundings should be submitted. This description should include a discussion of soil conditions, slopes, wetlands, waterways and vegetation on the site. Particular attention should be given to unique, unusual, or environmentally sensitive features and to those that provide particular opportunities or constraints for development.

3. Project Description and Site Plans

   A map (or maps) at the scale of the topographical base map indicating the location of existing and proposed buildings roads, parking areas, utilities, structural facilities for stormwater management and sediment control, and other permanent structures. The map(s) shall also clearly show areas where alterations will occur in the natural terrain and cover, including lawns and other landscaping, and seasonal high groundwater elevations. A written description of the site plan and justification for proposed changes in natural conditions shall also be provided.

4. Land Use Planning and Source Control Plan

   This plan shall provide a demonstration of how the goals and standards of Sections III through V are being met. The focus of this plan shall be to describe how the site is being developed to meet the objective of controlling groundwater recharge, stormwater quality and stormwater quantity problems at the source by land management and source controls whenever possible.

5. Stormwater Management Facilities Map

The following information, illustrated on a map of the same scale as the topographic base map, shall be included:

i. Total area to be disturbed, paved or built upon, proposed surface contours, land area to be occupied by the stormwater management facilities and the type of vegetation thereon, and details of the proposed plan to control and dispose of stormwater.
ii. Details of all stormwater management facility designs, during and after construction, including discharge provisions, discharge capacity for each outlet at different levels of detention and emergency spillway provisions with maximum discharge capacity of each spillway.

6. Calculations

i. Comprehensive hydrologic and hydraulic design calculations for the pre-development and post-development conditions for the design storms specified in Section IV of this ordinance.
ii. When the proposed stormwater management control measures depend on the hydrologic properties of soils or require certain separation from the seasonal high water table, then a soils report shall be submitted. The soils report shall be based on onsite boring logs or soil pit profiles. The number and location of required soil borings or soil pits shall be determined based on what is needed to determine the suitability and distribution of soils present at the location of the control measure.

7. Maintenance and Repair Plan

The design and planning of the stormwater management facility shall meet the maintenance requirements of Section X.

8. Waiver from Submission Requirements

The municipal official or board reviewing an application under this ordinance may, in consultation with the municipality's review engineer, waive submission of any of the requirements in Section IX.C.1 through IX.C.6 of this ordinance when it can be demonstrated that the information requested is impossible to obtain or it would create a hardship on the applicant to obtain and its absence will not materially affect the review process.

SECTION X: MAINTENANCE AND REPAIR.

A. Applicability

Projects subject to review as in Section I.C of this ordinance shall comply with the requirements of Section X.B and X.C.

B. General Maintenance

1. The design engineer shall prepare a maintenance plan for the stormwater management measures incorporated into the design of a major development.

2. The maintenance plan shall contain specific preventative maintenance tasks and schedules; cost estimates, including estimated cost of sediment, debris, or trash removal; and the name, address, and telephone number of the person or persons responsible for preventative and corrective maintenance (including replacement). The plan shall contain information on BMP location, design, ownership, maintenance tasks and frequencies, and other details as specified in Chapter 8 of the NJ BMP Manual, as well as the tasks specific to the type of BMP, as described in the applicable chapter containing design specifics.

3. If the maintenance plan identifies a person other than the property owner (for example, a developer, a public agency or homeowners' association) as having the responsibility for maintenance, the plan shall include documentation of such person's or entity's agreement to assume this responsibility, or of the owner's obligation to dedicate a stormwater management facility to such person under an applicable ordinance or regulation.

4. Responsibility for maintenance shall not be assigned or transferred to the owner or tenant of an individual property in a residential development or project, unless such owner or tenant owns or leases the entire residential development or project. The individual property owner may be assigned incidental tasks, such as weeding of a green infrastructure BMP, provided the individual agrees to assume these tasks; however, the individual cannot be legally responsible for all of the maintenance required.

5. If the party responsible for maintenance identified under Section X.B.3 above is not a public agency, the maintenance plan and any future revisions based on Section X.B.7 below shall be recorded upon the deed of record for each property on which the maintenance described in the maintenance plan must be undertaken.

6. Preventative and corrective maintenance shall be performed to maintain the functional parameters (storage volume, infiltration rates, inflow/outflow capacity, etc.) of the stormwater management measure, including, but not limited to, repairs or replacement to the structure; removal of sediment, debris, or trash; restoration of eroded areas; snow and ice removal; fence repair or replacement; restoration of vegetation; and repair or replacement of non-vegetated linings.

7. The party responsible for maintenance identified under Section X.B.3 above shall perform all of the following requirements:

i. maintain a detailed log of all preventative and corrective maintenance for the structural stormwater management measures incorporated into the design of the development, including a record of all inspections and copies of all maintenance-related work orders;
ii. evaluate the effectiveness of the maintenance plan at least once per year and adjust the plan and the deed as needed; and
iii. retain and make available, upon request by any public entity with administrative, health, environmental, or safety authority over the site, the maintenance plan and the documentation required by Section X.B.6 and B.7 above.

8. The requirements of Section X.B.3 and B.4 do not apply to stormwater management facilities that are dedicated to and accepted by the municipality or another governmental agency, subject to all applicable municipal stormwater general permit conditions, as issued by the Department.

9. In the event that the stormwater management facility becomes a danger to public safety or public health, or if it is in need of maintenance or repair, the municipality shall so notify the responsible person in writing. Upon receipt of that notice, the responsible person shall have fourteen (14) days to effect maintenance and repair of the facility in a manner that is approved by the municipal engineer or his designee. The municipality, in its discretion, may extend the time allowed for effecting maintenance and repair for good cause. If the responsible person fails or refuses to perform such maintenance and repair, the municipality or County may immediately proceed to do so and shall bill the cost thereof to the responsible person. Nonpayment of such bill may result in a lien on the property.

C. Nothing in this subsection shall preclude the municipality in which the major development is located from requiring the posting of a performance or maintenance guarantee in accordance with N.J.S.A. 40:55D-53.

D. Alteration of Maintenance Plan. Any alteration is maintenance responsibility or alterations to maintenance plans and agreements must be reviewed and approved by the Borough of Bogota Building Department Official or Board that reviewed the application under this Chapter in consultation with the borough engineer, superintendent of public works and building department official.

SECTION XI: PENALTIES.

A. Any person(s) who erects, constructs, alters, repairs, converts, maintains, or uses any building, structure or land in violation of this ordinance shall be subject to the following penalties:

1. Any person who is convicted for violating any of the provisions of this Chapter shall be subject to one (1) or more of the following: a fine of not more than two thousand ($2,000.00) dollars, imprisonment for any term not exceeding ninety (90) days, and/or a period of community service not exceeding ninety (90) days.
2. A separate offense or violation shall be deemed to be committed on each day that a violation occurs or continues.

B. Responsibility for Administration. The superintendent of the department of public works, borough engineer and building department official shall administer, implement and enforce the provisions of this Chapter. Any powers granted or duties imposed upon the superintendent of the department of public works, borough engineer or building department official may be delegated in writing to the person(s) or entities acting in the best interest of or in the employment of the Borough of Bogota.

C. Enforcement of Penalties and Liens. Should the applicant/owner fail to take the corrective actions, the Borough of Bogota shall then have the right to take the available appropriate remedies it deems necessary to correct the violations, and to assert a lien on the subject property in an amount equal to the costs of the remedial actions. The lien shall be enforced in the manner provided or authorized by law for the enforcement of common law liens on personal property. The lien shall be recorded with the Borough of Bogota and shall incur legal interest from the date of recording. The imposition of any penalty shall not exempt the offender from compliance with the provisions of this Chapter.

SECTION XII: SEVERABILITY.

Each section, subsection, sentence, clause and phrase of this Ordinance is declared to be an independent section, subsection, sentence, clause and phrase, and the finding or holding of any such portion of this Ordinance to be unconstitutional, void, or ineffective for any cause, or reason, shall not affect any other portion of this Ordinance.

SECTION XIII. EFFECTIVE DATE.

This Ordinance shall be in full force and effect from and after its adoption and any publication as required by law.